

MAY 28 1997

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 JAN 13 PM 2:48

For corners in

<u>LAPEER</u> <small>County</small>	Located In:	Corner Code ##
1. Public Land Survey DEERFIELD TWP	T <u>9N</u> R <u>10E</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, HAROLD N. ELRICH, in a field survey on APRIL 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1824 S. SIBLEY NORTH 83.80 INTERSECTED NORTH AT POST
- 1869 GILBERT BATES STAKE PINE 12 N 79 E 56, TAMARACK 9 S 29 E 37
- 1971 LELAND D. BATES P.S. #16699 LIBER 001, PAGES 97 & 98 FOUND NAIL SET 1/2" IRON N 85° W 29.1 FEET, TOP OF ANGLE IRON-NORTHEAST CORNER OF BRIDGE DECK, S 40° W 47.85 FEET, NAIL & CAP 12" TREE, S 75° E 86.3 FEET, NAIL & CAP 24" ELM, S 45° E 49.3 FEET, ROAD SIGN
- 1984 HAROLD N. ELRICH P.S. #18986 LIBER 006, PAGE 812, FOUND 1/2" IRON ROD IN MONUMENT BOX (NO WITNESSES SHOWN ON SURVEY)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996 HAROLD N. ELRICH P.S. #18986 FOUND 1/2" IRON IN MONUMENT BOX IN CENTERLINE OF FISH LAKE ROAD AND NORWAY LAKE ROAD. TREE LINE RUNNING TO THE WEST.

ACCEPTED 1/2" IRON FOUND AS BEST LOCATION OF ORIGINAL POSITION OF SOUTHWEST CORNER OF SECTION 36, T9N-R10E, DEERFIELD TOWNSHIP, LAPEER COUNTY, MICHIGAN

MEASURED REFERENCES - K-13 TO K-12 2673.32 FEET
K-13 TO K-2 2907.83 FEET (WEST 1/4 CORNER, SECTION 1, T8N-R10E, MAYFIELD TOWNSHIP)
K-13 TO L-13 2618.05 FEET

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 PLACED LAPEER COUNTY REMONUMENTATION CAP ON 1/2" IRON FOUND

SET NEW WITNESSES - N 40° W 27.82 FEET P.K. NAIL & WASHER IN GUARD RAIL POST
S 30° W 33.02 FEET P.K. NAIL & WASHER IN GUARD RAIL POST
S 40° E 72.62 FEET P.K. NAIL & WASHER IN 6" ELM
N 30° E 60.43 FEET P.K. NAIL & WASHER IN UTILITY POLE

LAPEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Signed by Harold N. Elrich
Surveyor's Michigan License No. 18986

Date 12-30-96 Ray Davis
DATE 9-10-96
DAVIS F.S. CO. SURVEYORS

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1977
REVISED MAY 14, 1975
REVISED JAN., 1983