

SURVEY & REMONUMENTATION

MAR 13 1998

**1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED RECORD
97 NOV 12 PM 2:56

SECTION

For corners in: **DEERFIELD TWP.**

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>09N</u> R <u>10E</u>	<u>M-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JONATHAN M. FIELD, in a field survey on JUNE 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1822 GLO; WAMPLER, D.S.; SET POST; BEECH 16 N57W 44LKS., BEECH 7 S41W 9LKS.
1971 KAY ENG.; KAY, P.S.#14096; SURVEY; L.001,PG.043; HANDHOLE; S45E 74.5' 4" PINE, S30E 136.95' 24" WILLOW, NORTH 81.4' R/W POST
1972 KAY ENG.; KAY, P.S.#14096; SURVEY; L.001,PG.794; NO OBJECT STATED; SAME WITS AS 1971 SURVEY
1975 SMITH SURVEYING; SMITH, P.S.#21582; SURVEY; L.003,PG.432-433; FND. MON BOX; NO WITS GIVEN
1976 BECK SURVEYING; BECK, P.S.#21559; SURVEY L.003,PG.577; NO OBJECT STATED; SAME WITS AS 1971 SURVEY
1979 BECK-GRAVLIN; GRAVLIN, P.S.#23510; SURVEY; L.005,PG.566; MON BOX; S53W 49.97' 16" MAPLE, N03E 36.22' 8" OAK, S15W 31.83' 19" MAPLE

M-2 TO M-1
M-2 TO M-3 2609.06' M.D.O.T.
M-2 TO L-2 2635.38' GRAVLIN '79; 2630.74' SMITH '75

PEER GROUP
APPROVED LAND CORNER
P.A. 345 OF 1990
LAPEER COUNTY

Jonathan M. Field
JONATHAN M. FIELD, P.S. CO. SURVEYOR
DATE 9-29-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 ROWE; FIELD, PS#37276; FND. 1/2" ROD IN MON. BOX 7.4' S. OF C/L ASPH. ROAD E-W AT APPROX. P.I. & ON OCC. TREE LINE N-S

NOTE: THIS CORNER HAS BEEN ACCEPTED BY PRACTICE AS BEING COMMON WITH A-2 T9N-R11E

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-2 1/2" ROD W/ STANDARD REMON CAP IN MON. BOX
S05°W, 29.33' TOP CENTER OF W. END 12" CONC. CULV.
S45°E, 36.47' TOP CENTER OF E. END 12" CONC. CULV.
S45°E, 74.22' P-K NAIL W/ REMON TAG IN SW FACE 14" WHITE PINE
NORTH, 81.4' S. FACE CONC. R.O.W. POST (81.95' TO CENTER)
N45°E, 40.33' 1/2" ROD W/ CAP #37276
N45°W, 40.89' 1/2" ROD W/ CAP #37276



Signed by *Jonathan M. Field* Date 11-11-97
Surveyor's Michigan License No. 37276

LIBER 0005 PAGE 0454