

SURVEY & REMONUMENTATION

APR 29 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
1995 REMONUMENTATION PROGRAM

For corners in DEERFIELD TWP.

Lapeer

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 09N R 10E M-4
- T R
- T R
- T R
- 2. Property Controlling in Section S T R
- S T R
- 3. Miscellaneous Property in Sec. S T R
- S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

RECEIVED FOR RECORD

95 DEC 28 PM 2:45

LIBER NO. 005 PAGE NO. 331

Melissa DeVough

REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

I, JONATHAN M. FIELD, in a field survey on MARCH 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1822 GLO; WAMPLER, D.S.; SET 1/2 MILE POST; MAPLE 11 N19W 19LKS., BEECH 17 S36 1/2W 17LKS.
- 1899 SICKLESTEEL, C.S.; SURVEY OF SEC.12; SET STONE 15x11x9; 1/4 POST OF SEC.7 T9N-R11E S1 3/4E 20LKS.
- 1972 ELRICH, P.S.#18986; LCRC; L.2, PG.11; FND 1/2" IRON; NORTH 10.02' 8" OAK, SOUTH 27.49' 12" BIRCH, WEST 12.53' 15" OAK
- 1972 HENDERSON-BATES; HENDERSON, P.S.#16043; SURVEY JOB #6196-A DATED 9-27-72; NO OBJECT STATED; SAME WITS AS 1972 LCRC ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1994 ROWE ENG.; FIELD, P.S.#37276; FND 1/2" ROD W/CAP #18986 AT FENCE CORNER (FENCES N-S-W) ALSO FND FENCE CORNER 18'± S. (FENCES S-E).


G.L.O. NOTES FOR T9N-R11E INDICATE THAT THIS CORNER IS NOT COMMON WITH A-4 T9N-R11E

- M-4 TO M-3 2636.74' (HENDERSON 1972)
- 2635.75' (REI 1995)
- M-4 TO M-5 2626.14' (REI 1995)

ACCEPTED FND ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-4 REPLACED FND ROD W/ 1/2" ROD AND STANDARD REMON CAP
- SOUTH, 27.38' SET NAIL W/REMON TAG IN NE FACE 14" BIRCH
- S20°E, 23.64' SET NAIL W/REMON TAG IN SW FACE 8" ASH
- EAST, 9.95' SET NAIL W/REMON TAG IN W. FACE 6" ELM
- N05°W, 10.10' SET NAIL W/REMON TAG IN W. FACE 12" MAPLE



Signed by Jonathan M. Field

DEER GROUP APPROVED LAND CORNER Date 12-1-95

Surveyor's Michigan License No. 37276

RAY DAVIS P.S. CO. SURVEYOR

RAY DAVIS P.S. CO. SURVEYOR DATE 8-31-95

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 44, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983

LIBER 0005 PAGE 0331