

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

**1994 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC 22 PM 2:00

LIBER NO. 05 PAGE NO. 176
Nelson D. Smith
REGISTER OF DEEDS
LANSING, MICHIGAN

For corners in DEERFIELD TWP. LAPEER (County)	Located In:	Corner Code #
1. Public Land Survey	T 09N R 10E	M-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JONATHAN M. FIELD, in a field survey on SEPTEMBER 23 1994
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1822 GLO; WAMPLER, D.S.; SET POST; IRONWOOD 6 N17W 42LKS., ELM 9 S83W 23LKS.
1906 SICKLESTEEL, C.S.; STAKE; BURR OAK 30 N34 1/2E 57LKS., ELM 22 S31 1/2W 55LKS.
1974 HENDERSON-BATES; ELRICH, P.S.#18986; SURVEY L.2, PG.668; FND 1/2"X 12" BOLT; S30°W 40.03'
12" BOXELDER, N45°E 46.78' 6" BOXELDER, N35°W 57.65' FE POST
1974 ELRICH, P.S.#18986; LCRC L.2, PG.541; FND 1/2"X 12" BOLT; SAME WITS AS 1974 SURVEY ABOVE
1976 HENDERSON-BATES; HENDERSON, P.S.#16043; SURVEY L.3, PG.748; FND 1/2"X 12" BOLT; SAME
WITS AS 1974 SURVEY ABOVE
1976 KAY ENG.; KAY, P.S.#14096; SURVEY L.3, PG.982; FND BOLT; SAME WITS AS 1974 SURVEY ABOVE
1977 BECK-GRAVLIN; GRAVLIN, P.S.#23510; SURVEY L.4, PG.144; NO OBJECT STATED; SAME WITS AS
1974 SURVEY ABOVE
1980 BECK-GRAVLIN; GRAVLIN, P.S.#23510; SURVEY L.5, PG.563; NO OBJECT STATED; SAME WITS AS
1974 SURVEY ABOVE
1984 HENDERSON-BATES; ELRICH, P.S.#18986; SURVEY L.6, PG.815; FND IRON SHAFT; S30°W 40.03' 12"
BOXELDER, N45°E 46.78' 10" BOXELDER, N35°W 58.30' 6" ELM, EAST 27.64' FE POST
1988 GRAVLIN, P.S.#23510; SURVEY L.7, PG.973; FND IRON SHAFT; SAME WITS AS 1984 SURVEY ABOVE
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994 ROWE ENG.; FIELD, P.S.#37276; FND 1/2"X 12" BOLT @ APPROX. C/L PI OF GRAVEL RD N-W & ON
LINE W/ FE TO E. GLO NOTES FOR T9N-R11E INDICATE THAT A-7 WAS SET 15 LKS. S. OF M-7
T9N-R10E HOWEVER THIS CORNER HAS BEEN USED AS COMMON TO BOTH TOWNSHIPS IN SEVERAL
SURVEYS; FND NO EVIDENCE OF ANOTHER CORNER; FND 2 PREVIOUS WITNESSES INDICATING
THAT FND BOLT IS IN SAME POSITION AS 1974 HENDERSON-BATES SURVEY

2634.85' M-7 TO M-8 (MEAS. BY OTHERS)
2640.34' M-7 TO M-6 (MEAS. BY OTHERS)

ACCEPTED 1/2" BOLT AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION
LAPEER CO. PEER GROUP ACCEPTED 1/2" BOLT AS ALSO BEING A-7 T9N-R10E

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-7 REMOVED BOLT, SET 1/2" ROD W/ STANDARD BRASS CAP
SOUTH, 6.42' W. EDGE OF W. SIGN POST LEG
S33°W, 40.03' FND NAIL W/FLAG. IN SE FACE 18" BASSWOOD
N44°E, 46.74' FND NAIL W/FLAG. IN S. FACE 16" BOXELDER
EAST, 27.69' SET NAIL W/ REMON TAG IN S. FACE FE POST
S41°E, 34.04' FND NAIL W/FLAG. IN NE FACE FE POST

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990

Signature: *Jonathan M. Field*
LANSING COUNTY SURVEYOR
Michigan License No. 37276

Date 12-8-94

RAY DAVIS, P.S. L.C. SURVEYOR
DATE 12-22-94

LIBER 0005 PAGE 0176

