

**SURVEY &  
REMONUMENTATION**

APR 28 1995

COMMISSION

**1994 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC 22 PH 2:01

LIEER NO. 05 INDEX NO. 177  
*Melissa D. Smith*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

For corners in DEERFIELD TWP.  
LAPEER (County) Located In: Corner Code #

1. Public Land Survey	T 09N R 10E	M-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on SEPTEMBER 23 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 1822 GLO; WAMPLER, D.S.; SET 1/2 MILE POST; IRONWOOD 14 S2W 32LKS., IRONWOOD 7 N54W 17LKS.  
 1906 SICKLESTEEL, C.S.; STAKE 2 STONES; PINE 44 N54W 41 1/2LKS., PINE 40 S28W 57LKS.  
 NOTE ON SURVEY - E1/4 POST 19,9,11 NORTH 7 1/2  
 1972 HENDERSON-BATES; HENDERSON, P.S.#16043; SURVEY L.1, PG.758; SET 1/2" IRON ROD; N65°E 44.84' 6" OAK, N50°W 30.48' 6" MAPLE, S70°W 91.79' 10" ELM  
 1972 HENDERSON, P.S.#16043; LCRC L.1, PG.599; SET 1/2" IRON ROD IN GRAVEL ROAD INTERSECTION 1/2 WAY BETWEEN RIGHT OF WAY FENCES; SAME WITS AS 1972 SURVEY ABOVE  
 1976 KAY ENG.; KAY, P.S.#14096; SURVEY L.3, PG.982; FND 1/2" IRON ROD; SAME WITS AS 1972 SURVEY ABOVE  
 1978 BECK-GRAVLIN; GRAVLIN, P.S.#23510; SURVEY L.4, PG.948; NO OBJECT STATED; NO WITS GIVEN  
 1984 GRAVLIN, P.S.#23510; SURVEY L.6, PG.749; FND 1/2" IRON; S45°E 41.27' T.POLE, N20°E 21.44' 8" OAK, N40°W 32.80' 10" MAPLE  
 1989 GRAVLIN, P.S.#23510; LCRC L.4, PG.255; FND 1/2" IRON; SAME WITS AS 1984 SURVEY ABOVE  
 B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1994 ROWE ENG.; FIELD, P.S.#37276; FND 1/2" ROD (BENT & TWISTED) @ C/L - C/L GRAVEL ROADS E-W-S RECOVERED 2 PREVIOUS WITNESSES INDICATING THAT FND ROD IS IN SAME POSITION AS 1972 HENDERSON-BATES SURVEY

2635.06' M-8 TO M-9 (MEAS. BY OTHERS)  
 2634.85' M-8 TO M-7 (MEAS. BY OTHERS)

ACCEPTED 1/2" ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION  
 LAPEER CO. PEER GROUP ACCEPTED 1/2" ROD AS ALSO BEING A-8 T9N-R11E

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 M-8 REMOVED BENT ROD, SET 1/2" ROD W/ STANDARD BRASS CAP  
 N35°W, 32.56' SET NAIL W/ REMON TAG IN SW FACE 10" MAPLE  
 S67°W, 83.38' SET NAIL W/ REMON TAG IN N. FACE GUY POLE  
 S41°E, 41.31' SET NAIL W/ REMON TAG IN SW FACE CUT-OFF T.POLE  
 N21°E, 25.55' SET NAIL W/ REMON TAG IN NW FACE 10" OAK  
 N65°E, 44.8' CENTER OF CLUSTER OF SMALL OAKS  
 S70°W, 91.5' ROTTED ELM STUMP

PEER GROUP  
 APPROVED LAND CORNER  
 PA 345 OF 1990  
 LAPEER COUNTY

Signed by Jonathan M. Field  
 JAY DAVIS  
 Surveyor Michigan License No. 37276  
 DATE 12-22-94

Date 12-8-94

