

SURVEY &
REMONUMENTATION

1993

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

COMMISSION
For corners in

LAPEER
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|----------------------------|-------------|
| 1. Public Land Survey | T <u>9</u> N R <u>10</u> E | <u>M-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

94 JAN - 6 PM 12: 54
LIBER 005 FILE NO. 61
Michigan Files
RECORDS
LAPEER COUNTY

Register of Deeds Stamp & File Number

I, Jonathan M. Field, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
 1822 GLO- Wampler, D.S.; Set 1/2 mile post; Ash 8" N44½W 11 lks., Ash 9" S42W 35lks.
 1906 Sickledsted, C.S; Stake, Pine 30" N46E 31 lks., Pine 30" N24W 23lks.
 1978 Gravlin, P.S.#23510; Survey L.4,Pg.548 - Fnd 1/2" iron
 1978 Gravlin, P.S.#23510; Survey L.4,Pg.672 - 1/2" iron; same wits as prev. 1978 survey
 1980 Gravlin, P.S.#23510; Survey L.5,Pg.789 - no object stated; same wits as 1978 survey
 1987 Gravlin, P.S.#23510; Survey L.7,Pg.734 - no object stated; same wits as 1978 survey
 1989 Gravlin, P.S.#23510; LCRC L.4,Pg.226 - Fnd. 1/2" iron; same wits as 1978 survey
 1991 Elrich, P.S.#18986; LCRC L.4,Pg.413 - Fnd. 1/2" iron 6' +/- W. of c/l; 2 prev. wits verify position same as 1978 survey
 1992 Elrich, P.S.#18986; Survey L.9,Pg.923 - Fnd. 1/2" iron; wits same as 1991 LCRC
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1993 Rowe Eng. - Field, P.S.#37276; Fnd. 1/2" rod 5'W & 1'S of c/l intersection of gravel roads N-S-E-W
 Fnd. 2 previous wits which verify that rod is in same position as 1978 Gravlin survey
 Accepted fnd 1/2" rod as best evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-10 1/2" rod w/ standard brass cap
 S59°E, 59.96' Set nail w/remon tag in NE face T.pole
 S68°W, 83.54' Set nail w/remon tag above fnd nail w/flag. in N. face T.pole
 N20°W, 123.74' Set nail w/remon tag in SW face P.pole
 N29°E, 70.95' Fnd. nail w/flag. in E. face 24" Oak
 N40°E, 48.5' Center of 24" stump
 S45°E, 57.48' Set nail w/remon tag above fnd nail w/flag. in SW face 10" Elm
 N56°W, 33.34' Set nail w/remon tag in top of guard rail post

Signed by Jonathan M. Field
 Surveyor's Michigan License No. 37276

Date 11-24-93

