

SURVEY & REMONUMENTATION

1993

COMMISSION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD

For corners in

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9</u> N R <u>10E</u>	<u>M-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

94 JUN -6 PM 12:57
LIBER 005 66-67
Michigan Files 67
REGISTERED FILES
LAPEER MICHIGAN
Register of Deeds Stamp & File Number

I, Jonathan M. Field, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1822 GLO- Wampler, D.S.; Set post; Tamarack 12" N41½E 11 lks., Tamarack 13" N36½W 12 lks.
1971 Henderson, P.S.#16043; Survey L.1, Pg.178 - no object stated, 2 wits given
1972 Henderson, P.S.#16043; LCRC L.1, Pg.205 - fnd 1/2" rod, same wits as 1971 survey
1972 Elrich, P.S.#18986; Survey L.1, Pg.444 - fnd 1/2" iron same wits as 1971 survey
1973 Henderson, P.S.#16043; LCRC L.2, Pg.275 - fnd rod, 2 of 5 wits same as 1971 survey
1974 Kay, P.S.#14096; Survey L.2, Pg.589 - no object stated, 1 wit same as 1973 LCRC
1974 Kay, P.S.#14096; Survey L.3, Pg.52 - fnd 1/2" iron, same wits as 1971 survey; also the following surveys by Kay Eng. have same 2 wits as 1971 survey: L.3, Pg.143; L.3, Pg.145
Section A. continued on back.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1993 Rowe Eng.- Field, P.S.#37276; fnd 1/2" rod 1'N of centerline of gravel road E-W
Fnd. 2 previous wits. which verify that rod is in the same position as 1971 survey
Accepted fnd rod as best evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-13 1/2" rod w/ standard brass cap
N02°E, 45.40' Set nail w/remon tag above fnd nail w/flag. in W. face 10" Maple
N58°E, 34.49' Set nail w/remon tag above fnd nail w/flag. in S. face 30" Maple
N35°W, 28.30' Set nail w/remon tag above fnd P-K nail w/disc in SW face 8" Elm
S43°E, 31.75' Fnd. P-K nail w/disc in NE corner of 6x8 wood fence corner post fence S-E-W
N72°W, 72.42' Set nail w/remon tag in S. face 10" Maple
North, 33.00' Fnd. 1/2" rod w/cap #18986
West, 50'+/- Centerline of creek

Signed by Jonathan M Field Date 11-24-93
Surveyor's Michigan License No. 37276

JONATHAN M. FIELD
LAND SURVEYOR
No. 37276

A.(cont.)

L.3,Pg.141; L.3,Pg.872 (1976); L.3,Pg.880 (1976)

1977 Gravlin, P.S.#23510; Survey L.4,Pg.530 - no object stated, same wits as 1971 survey
 1978 Elrich, P.S.#18986; Survey L.4,Pg.569 - fnd 1/2" rod, 2 wits same as 1971 survey
 1980 Getz, P.S.#25843; Survey L.5,Pg.690 - fnd 1/2" iron, 2 wits same as 1971 survey
 1981 Beck, P.S.#21559; Survey L.6,Pg.34 - no object stated, 2 wits same as 1971 survey
 1981 Gravlin, P.S.#23510; Survey L.6,Pg.203 - fnd 1/2" iron, 2 wits same as 1971 survey
 1982 Gravlin, P.S.#23510; Survey L.6,Pg.257 - fnd 1/2" iron, 2 wits same as 1971 survey
 1988 Gravlin, P.S.#23510; LCRC L.4,Pg.168 - fnd 1/2" iron, 2 wits same as 1971 survey
 1989 Gravlin, P.S.#23510; LCRC L.4,Pg.246 - fnd 1/2" iron, same 2 wits as 1971 survey
 1992 Elrich, P.S.#18986; Survey L.10,Pg.85 - fnd 1/2" iron, 1 wit same as 1971 survey

2.00	REMOVAL
9.00	MISC D
9.00	REMOVAL