

**SURVEY & REMONUMENTATION**

MAR 13 1998

SECTION

**1997 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
97 NOV 12 PM 2:55

For corners in: **NORTH BRANCH TWP.**

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>09N</u> R <u>11E</u>	<u>A-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____ Recorded Plat _____		
5. Private Claims _____		

*Melissa De Vaughn*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN  
**Register of Deeds Stamp & File Number**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JUNE 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 1833 GLO; PARKE, D.S.; SET POST; MAPLE 16 S26W 52LKS., BEECH 12 N63E 37LKS.  
 1971 KAY ENG.; KAY, P.S.#14096; SURVEY; L.001,PG.043; 1/2" IRON; N60W 34.6' 24" MAPLE, S45E 42.1' 20" MAPLE, S45W 38.2' 24" MAPLE  
 1975 SMITH SURVEYING; SMITH, P.S.#21582; SURVEY; L.003,PG.432-433; FND. IRON; NO WITS GIVEN  
 1978 BECK-GRAVLIN; GRAVLIN, P.S.#23510; SURVEY L.004,PG.676; NO OBJECT STATED; N60W 34.74' NAIL IN 24" MAPLE, S45E 42.10' NAIL IN 20" MAPLE, SOUTH 23.00' NAIL IN 16" ASH  
 1987 HENDERSON-BATE; ELRICH, P.S.#18986; SURVEY; L.007,PG.718; FND. 1/2" IRON; SAME WITS AS 1978 SURVEY  
 1988 GRAVLIN, P.S.#23510; SURVEY; L.007,PG.885; FND. 1/2" IRON; SAME WITS AS 1978 SURVEY ABOVE  
 1993 FIELD, P.S.#37276; 1993 REMON LCRC FOR M-13 T10N-R10E; FND. 1/2" ROD  
 M-1 TO L-1 2642.52' GRAVLIN '88 & '78; SMITH '75

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1997 ROWE; FIELD, PS#37276; FND. 1/2" W/ STANDARD REMON CAP RECOVERED ALL 1993 REMON WITS CITED ABOVE

NOTE: THIS CORNER IS COMMON WITH M-1 T9N-R10E, M-13 T10N-R10E, AND A-13 T10N-R11E

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 A-1 1/2" ROD W/ STANDARD REMON CAP

- S63°E, 77.94' NAIL W/ REMON TAG IN NE FACE CUT-OFF T. POLE
- S48°E, 42.61' NAIL W/ REMON TAG IN SW FACE 26" MAPLE
- S02°W, 23.87' NAIL W/ REMON TAG IN W. FACE 14" ASH
- N06°W, 25.99' NAIL W/ REMON TAG IN E. FACE 10" ASH
- N47°W, 35.49' NAIL W/ REMON TAG IN SW FACE 30" MAPLE



Signed by Jonathan M. Field  
 Surveyor's Michigan License No. 37276

APPROVED LAND CORNER  
 LAPEER COUNTY  
 DATE 11-11-97

LIBER 0005 PAGE 0453

RAY DAVIS P.S. CO. SURVEYOR  
 DATE 9-29-97