

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

**1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

For corners in: **NORTH BRANCH TWP.**

97 NOV 12 PM 2:57

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>09N</u> R <u>11E</u>	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____ Recorded Plat _____		
5. Private Claims _____		

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JUNE 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1822 GLO; WAMPLER, D.S.; SET POST; BEECH 16 N57W 44LKS., BEECH 7 S41W 9LKS.
 - 1971 KAY ENG.; KAY, P.S.#14096; SURVEY; L.001,PG.043; HANDHOLE; S45E 74.5' 4" PINE, S30E 136.95' 24" WILLOW, NORTH 81.4' R/W POST
 - 1972 KAY ENG.; KAY, P.S.#14096; SURVEY; L.001,PG.794; NO OBJECT STATED; SAME WITS AS 1971 SURVEY
 - 1975 SMITH SURVEYING; SMITH, P.S.#21582; SURVEY; L.003,PG.432-433; FND. MON BOX; NO WITS GIVEN
 - 1976 BECK SURVEYING; BECK, P.S.#21559; SURVEY L.003,PG.577; NO OBJECT STATED; SAME WITS AS 1971 SURVEY
 - 1979 BECK-GRAVLIN; GRAVLIN, P.S.#23510; SURVEY; L.005,PG.566; MON BOX; S53W 49.97' 16" MAPLE, N03E 36.22' 8" OAK, S15W 31.83' 19" MAPLE

- M-2 TO M-1
- M-2 TO M-3 2609.06' M.D.O.T.
- M-2 TO L-2 2635.38' GRAVLIN '79; 2630.74' SMITH '75

REGISTERED PROFESSIONAL SURVEYOR
JONATHAN M. FIELD
DATE 9-29-97

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1997 ROWE; FIELD, PS#37276; FND. 1/2" ROD IN MON. BOX 7.4' S. OF C/L ASPH. ROAD E-W AT APPROX. P.I. & ON OCC. TREE LINE N-S

NOTE: THIS CORNER HAS BEEN ACCEPTED BY PRACTICE AS BEING COMMON WITH M-2 T9N-R10E

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- A-2 1/2" ROD W/ STANDARD REMON CAP IN MON. BOX
 - S05°W, 29.33' TOP CENTER OF W. END 12" CONC. CULV.
 - S45°E, 36.47' TOP CENTER OF E. END 12" CONC. CULV.
 - S45°E, 74.22' P-K NAIL W/ REMON TAG IN SW FACE 14" WHITE PINE NORTH, 81.4' S. FACE CONC. R.O.W. POST (81.95' TO CENTER)
 - N45°E, 40.33' 1/2" ROD W/ CAP #37276
 - N45°W, 40.89' 1/2" ROD W/ CAP #37276



Signed by Jonathan M. Field Date 11-11-97
Surveyor's Michigan License No. 37276