

MAR 23 2000

REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

RECEIVED FOR RECORD

99 DEC 14 AM 9:15

<u>Lapeer</u> (County)	Located In: North Branch Twp.	Corner Code # <u>A-3</u>
1. Public Land Survey	T <u>9N</u> R <u>11E</u>	<u>A-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Melissa [Signature]  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

521

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A B C D E F G H I J K L M

1						
2	6	5	4	3	2	1
3						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9						
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						

I, Earl E. Gravlin, in a field survey on July 23 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1834 Burnham, int range line 40 links (26.4') South set post, birch 14 N58E 46, birch 10 S48E 24. County Surveyor: nothing. 1990 Gravlin L8 P578-579, found 1" pipe, S5E 22.6' 18" oak, S45E 32.72' 20" oak, N35W 28.36' 10" oak. 1993 Gravlin L10 P130, found 1" pipe, S5E 22.6' 18" oak, S45E 32.72' 20" oak, N35W 28.36' 10" oak. 1995 Field L5 P311 Act 74, set standard brass cap on fnd 1/2" rod, S27E 43.56' set nail w/remon tag above fnd nail w/flag NE face 14" oak, S10E 35.00' set nail w/remon tag above fnd nail w/flag SW face 16" oak, N51W 18.51' set nail w/remon tag above fnd nail w/flag NE face 14" oak, N18E 7.40' set chis. + on large stone, N43E 36.80' set nail w/remon tag SE face 38" oak, S50E 51.90' set nail w/remon tag NE face 24" oak, S03E 12.59' fnd 1/2" rod, S01E 17.82' fnd 1/2" rod.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron on centerline of extended gravel road to the East  
 Found two witnesses from previous surveys.  
 1/2" iron 33' North  
 Accepted found rod as perpetuation of original corner.  
 A-3 to A-2 2657.72'  
 A-3 to A-4 2634.46'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3 section corner common to sections 6, 7  
 Set standard brass cap on found 1/2" rod  
 N34E 46.58' found nail and tag in NE face 24" oak  
 N63E 56.02' found nail and tag in W face 24" oak  
 S61E 44.81' found nail and tag in NE face 24" oak  
 S44E 32.58' found nail and tag in SW face 16" oak  
 S11E 22.61' found nail and tag in NE face 14" oak  
 N1E 12.62' M-3 T9N-R10E  
 North 33.00' found iron & cap #23510



PEER GROUP  
 APPROVED LAND CORNER  
 PA 845 OF 1990  
 LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR  
 DATE 10-21-99

Signed by [Signature] Date 12-2-99  
 Surveyor's Michigan License No. 23510

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975  
REVISED JAN. 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993