

MAR 23 2000

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

RECEIVED FOR RECORD

99 DEC 14 AM 9:15

Lapeer

(County)

Located In: North Branch Twp.

Corner Code #

Melissa - [Signature]

REGISTER OF DEEDS LAPEER COUNTY, MICHIGAN

522

Register of Deeds Stamp & File Number

1. Public Land Survey	T	9N	R	11E	A-6
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A B C D E F G H I J K L M

1						
2	6	5	4	3	2	1
3						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9						
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						

I, Earl E. Gravlin, in a field survey on July 23 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: not set. County Surveyor: 1867 Bates, stake, Pine 24 N7E 32, Pine 22 S27W 19. 1979 Elrich L5 P417, found 5/8" iron (common to E 1/4 cor sec13 T9N-R11E), N70W 55.6' 48" oak, N50W 53.05' 20" oak, N40E 35.01' gate post. 1989 Elrich L8 P597, N70W 55.51' spike 46" oak, N50W 53.00' spike 24" oak, N40E 27.09' South gate post. 1992 Gravlin L9 P987, found iron, N50W 53.00' spike 24" oak, N40E 27.09' South gate post, N70W 55.51' spike 46" oak, A-6 to A-7 2640.84'. 1993 Gravlin L10 P254, found 5/8" rerod, N45E 36.06' North gate post, N80E 27.09' South gate post, N50W 53.00' spike in 24" oak. 1994 Field L5 P175 Act 74, set standard brass cap on 1/2" rod, N77W 55.44' set nail w/remon tag in E face twin 24" oak, N41W 52.86' set nail w/remon tag in NE face 22" oak, East 25.83' set nail w/remon tag in N face fe post, East 33.00' fnd 1/2" rod w/cap #18986, S61E 30.16' set nail w/remon tag above fnd nail w/flag in W face 14" maple. 1997 Gravlin L12 P359, found 5/8" rerod, N45E 36.05' North gate post, N80E 27.09' South gate post, N50W 53.00' spike in 24" oak. 1997 Kay job #97-133, fnd brass cap, N70W 55.60' 48" oak, N50W 53.05' 20" oak, N40E 35.01' gate post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod w/standard brass cap on centerline of road.
 A-6 to A-5 2638.87'
 A-6 to A-7 2634.85'
 M-6 T9N-R10E accepted by peer group as common to A-6.
 Accepted 1/2" rod with brass cap as a perpetuation of the original corner position.
 Peer group accepted M-6 T9N-R10E as also being A-6 T9N-R11E.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 West quarter corner section 18
 Found standard brass cap on 1/2" rod
 N77W 55.44' found nail w/remon tag E face twin 24" oak
 N41W 52.86' found nail w/remon tag in NE face 22" oak
 East 25.83' found nail w/remon tag in N face fence post
 East 33.00' 1/2" rod with cap #18986
 S61E 31.60' found nail w/remon tag above nail w/flag W face 14" maple

PEER GROUP APPROVED LAND CORNER
 MAR 23 2000
 LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR

Signed by [Signature] Date Dec 2, 1999
 Surveyor's Michigan License No. 23510

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
 REVISED JAN. 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1988