

MAR 23 2000

REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

RECEIVED FOR RECORD

99 DEC 14 AM 9:16

Lapeer Located in: Corner Code #
 (County) North Branch Twp. A-8

1. Public Land Survey	T	<u>9N</u>	R	<u>11E</u>	
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Melissa [Signature]
 REGISTER OF DEEDS
 LAPEER COUNTY, MICHIGAN

524

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

A B C D E F G H I J K L M

1						
2	6	5	4	3	2	1
3						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9						
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						

I, Earl E. Gravlin, in a field survey on July 23 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: not set. County Surveyor: 1866 Bates, stake, pine 36 S45W 52, pine 48 N47W 46 1/2; 1905 Sichelsteel, found stone, pine stump 38 N46 1/4W 45, 1/4 post East side sec 24 T9N-R10E (stone 15x9x6) N2W 6. 1984 Gravlin L6 P749, found 1/2" iron, S45E 41.27' bolt tel pole, N20E 21.44' 8" oak, N40W 32.80' 10" maple. 1986 Gravlin L7 P429, same as L6 P749. 1989 Gravlin L4 P255 Act 74, same as L6 P749. 1994 Field L5 P177 Act 74, removed bent rod, set 1/2" rod w/standard brass cap, N35W 32.56' set nail w/remon tag in SW face 10" maple, S67W 83.38' set nail w/remon tag in N face guy pole, S41E 41.31' set nail w/remon tag in SW face cut-off t. pole, N21E 25.55' set nail w/remon tag in NW face 10" oak, N65E 44.8' center of cluster of small oaks, S70W 91.5' rotted elm stump. 1997 Kay job #97-125A, find 1/2" steel stake, S45E 41.27' bolt t. pole, N20E 21.44' 8" oak, N40W 32.80' 10" maple. 1998 Kay L12 P580, same as 1997 Kay survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found standard brass cap on 1/2" iron on centerline of road.
 Witnesses match M-8 T9N-R10E except cut off telephone pole is gone.
 Accepted rod as a perpetuation of original corner.
 M-8 T9N-R10E accepted by peer group as common to A-8.
 A-8 to A7 2640.34' 2640.84'
 A-8 to A-9 2635.06' 2635.02'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 quarter corner section 19
 Found standard brass cap on 1/2" rod.
 N35W 32.56' found nail w/remon tag in SW face 10" maple
 S67W 83.38' found nail w/remon tag in N face guy pole
 N21E 25.55' found nail w/remon tag in NW face 10" oak
 N65E 44.8' center of cluster of small oaks
 S70W 91.5' rotted elm stump

APPROVED LAND CORNER GROUP
 APPROVED LAND CORNER
 PA 046 OF 1000
 LAPEER COUNTY

Signed by [Signature] Date DEC 2 1999
 Surveyor's Michigan License No. 23510

[Signature]
 RAY DAVIS P.S. CO. SURVEY

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
 REVISED JAN., 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1983