

MAR 23 2000

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

RECEIVED FOR RECORD

99 DEC 14 AM 9:16

<u>Lapeer</u> (County)	Located In: North Branch Twp.	Corner Code # <u>A-9</u>
1. Public Land Survey	T <u>9N</u> R <u>11E</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Melissa W. Vaughn
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

525

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Earl E. Gravlin, in a field survey on July 23 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO: 1834 Burnham, on range line set stake, pine 24 N89E 34, pine 14 S49E 13; Wampler, beech 14 N6W 32, beech 17 S41W 19.
County Surveyor: 1905 Sichelsteel, fnd stake and remains of old stake, set stone 19x16x16. 1974 Elrich L3 P75, found 1/2" iron. 1978 Gravlin L4 P674, N75W 30.56' nail & disk in fence post, East 42.35' nail 22" twin cherry, N65E 29.50' nail fence post. 1991 Gravlin L4 P370 Act 74, found 1/2" iron, same as L4 P674. 1994 Field L5 P178 Act 74, removed old rod, set 1/2" rod w/standard brass cap, East 42.42' set nail w/remon tag in N face twin 24" cherry, N40E 33.70' set nail w/remon tag in NW face fence post, N68W 30.49' fnd nail w/disk in NE face fe post, N81W 72.44' set nail w/remon tag in S face p pole, S18W 114.81' set nail w/remon tag in E face p pole. 1997 Kay job #97-125A, found 1/2" steel stake, N75W 30.56' nail & disk fnc post, East 42.35' nail 22" twin cherry, N65E 29.50' nail fnc post 1998 Kay L12 P580, same as 1997 Kay survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found standard brass cap on 1/2" iron on centerline of road.
Witnesses match A-9 T9N-R10E except N68W to a fence post is gone.
Accepted rod as a perpetuation of original corner.
M-9 T9N-R10E accepted by peer group as common to A-9.
A-9 to A-8 2635.06'
A-9 to A-10 2639.36' 2639.26'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-9 section corner common to sections 19, 30
Found standard brass cap on 1/2" rod
East 42.42' found nail w/remon tag in N face twin 24" cherry
N40E 33.70' found nail w/remon tag in NW face fence post
N81W 72.44' found nail w/remon tag in S face power pole
S18W 114.81' found nail w/remon tag in E face power pole

PEER GROUP
APPROVED LAND CORNER
PA 245 OF 1980
LAPEER COUNTY

Signed by [Signature] Date DEC 2, 1999
Surveyor's Michigan License No. 23510

RAY DAVIS P.S. CO. SURVEYOR

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JUNE 28, 1975

REVISED MAY 24, 1978
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993