

MAR 23 2000

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Lapeer</u> (County)	Located In: North Branch Twp.	Corner Code # <u>A-10</u>
1. Public Land Survey	T <u>9N</u> R <u>11E</u>	<u>_____</u>
	T <u>_____</u> R <u>_____</u>	<u>_____</u>
	T <u>_____</u> R <u>_____</u>	<u>_____</u>
	T <u>_____</u> R <u>_____</u>	<u>_____</u>
2. Property Controlling in Section	S <u>_____</u> T <u>_____</u> R <u>_____</u>	<u>_____</u>
	S <u>_____</u> T <u>_____</u> R <u>_____</u>	<u>_____</u>
3. Miscellaneous Property in Sec.	S <u>_____</u> T <u>_____</u> R <u>_____</u>	<u>_____</u>
	S <u>_____</u> T <u>_____</u> R <u>_____</u>	<u>_____</u>

RECEIVED FOR RECORD

99 DEC 14 AM 9:16

Melissa [Signature]
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

526

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Earl E. Gravlin, in a field survey on July 23 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: not set. County Surveyor: 1866 Bates, pine 30 N46E 31, pine 30 N24W 33; 1905 Sickelsteel, found stake, pine stump 20 N13W 88 1/2. 1974 Elrich L3 P76, N45E 48.84' 24" locust, S45W 48.62' 6" box elder, S70W 83.62' t pole. 1974 Elrich L2 P787-788 Act 74, set 1/2" iron, same as L3 P76. 1978 Gravlin L4 P674, same as L3 P76. 1978 Elrich L4 P236, same as L4 P674. 1991 Gravlin L9 P542, same as L4 P674. 1993 Field L5 P61, 1/2" rod w/standard brass cap, S59E 59.96' set nail w/remon tag in NE face t pole, S68W 83.54' set nail w/remon tag above find nail w/flag in N face t pole, N20W 123.74' set nail w/remon tag in SW face p pole. N29E 70.95' find nail w/flag in E face 24" oak, N40E 48.5' cen 24" stump, S45E 57.48' set nail w/remon tag above find nail w/flag in SW face 10" elm, N56W 33.34' set nail w/remon tag in top of guard rail post. 1994 Elrich L10 P682, N45W 33.40' LC ref tag top guard post, S70W 83.62' LC ref tag N face u p N10W 123.75' LC tag W face u p, S60E 60.00' LC tag N face u p, fd brass cap & iron rod. 1996 Gravlin L11 P476-478, same as L10 P682. 1997 Gravlin L 12 P204, same as L10 P682.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found standard brass cap on 1/2" iron on centerline of road.
Witnesses match A-10 to N-R10E except 24" stump is gone.
Accepted rod as a perpetuation of original corner.
M-10 T9N-R11E common to A-10.
A-10 to A-9 2639.36' 2639.26'
A-10 to A-11 2639.32'

PEER GROUP
APPROVED LAND CORNER
PAGE 03 OF 1990
LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR
DATE 10-21-99

C. Description of monument for corner and accessories established to perpetuate locating the

A-10 West quarter corner section 30
Found standard brass cap on 1/2" rod
S59E 59.96' found nail w/remon tag in NE face t pole
S68W 83.54' found nail w/remon tag above find nail w/flag in N face tele pole
N20W 123.74' found nail w/remon tag in SW face power pole
N29E 70.95' found nail w/flag in E face 24" oak
S45E 57.48' found nail w/remon tag above find nail w/flag in SW face 10" elm
N56W 33.34' found nail w/remon tag in top of guard rail post



Signed by [Signature] Date DEC 2 1999
Surveyor's Michigan License No. 23510

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993