

10-21
 SURVEY &
 REMONUMENTATION

MAR 23 2000

REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

RECEIVED FOR RECORD

99 DEC 14 AM 9:16

Lapeer Located In: North Branch Twp. Corner Code # _____
 (County) North Branch Twp.

1. Public Land Survey	T <u>9N</u>	R <u>11E</u>	<u>A-11</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

Melissa [Signature]
 REGISTER OF DEEDS
 LAPEER COUNTY MICHIGAN

527

Register of Deeds Stamp & File Number

A B C D E F G H I J K L M

1						
2	6	5	4	3	2	1
3						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9						
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						

I, Earl E. Gravlin, in a field survey on July 23 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1834 Burnham, int W line at stake, maple 8" N28E 35, pine 10 S31E 22. County Surveyor: nothing. 1974 Kay L3 P3-4, E 39.50' 8" aspen, N35W 30.03' 8" maple, S40W 31.55' 36" maple, fnd 1/2" iron. 1974 Elrich L3 P76, E 39.64' 10" poplar, S65W 31.58' 36" maple, N40W 30.05' 8" maple clump. 1974 Elrich L2 P787 Act 74, same as L3 P76. 1978 Henderson L4 P836, same as L2 P76. 1978 Elrich L5 P316, same as L2 P76. 1974 Kay job #74-260, fd 1/2" iron, East 39.50' 8" aspen, N35W 30.05' 8" maple, S40W 31.55' 36" maple. 1986 Henderson L7 P461, same as L3 P76. 1991 Gravlin L9 P542, same as L3 P76. 1993 Gravlin L10 P152, same as L3 P76. 1993 Field L5 P62 Act 74, 1/2" rod w/standard brass cap, N47E 29.00' set nail w/remon tag above fnd nail w/flag NW face twin 8" ash, N78E 31.89' set nail w/remon tag above fnd nail w/flag SE face 10" poplar, S48W 31.74' set nail w/remon tag below fnd nail w/flag E face 36" maple, West 67.89' set nail w/remon tag above fnd nail w/flag S face pp, N31W 30.27' set nail w/remon tag above fnd nail w/flag NE face 6" maple clump. 1995 Gravlin L11 P476, fnd brass cap & iron, N47E 29.00' nail 8" ash, N78E 31.89' 10" poplar, S48W 31.74' 36" maple. 1997 Gravlin L12 P108, same as L11 P476. 1997 Gravlin L12 P239, same as L11 P476.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

Found standard brass cap on 1/2" iron on centerline of road.
 Witnesses match M-11 T9N-R10E.
 Accepted rod as a perpetuation of original corner.
 M-11 T9N-R10E common to A-11.
 A-11 to A-10 2639.32'
 A-11 to A-12 2629.10'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

A-11 section corner common to sections 30, 31 and sections 25, 36 T9N-R10E
 Found standard brass cap on 1/2" rod
 N47E 29.00' found nail w/remon tag above fnd nail w/flag NW face twin 8" ash
 N78E 31.89' found nail w/remon tag above fnd nail w/flag SE face 10" poplar
 S48W 31.74' found nail w/remon tag below fnd nail w/flag E face 36" maple
 West 67.89' found nail w/remon tag above fnd nail w/flag S face power pole
 N31W 30.27' found nail w/remon tag above fnd nail w/flag NE face 6" maple in clump



DEED GROUP
 APPROVED LAND CORNER
 PA 245 OF 1000
 LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEY
 DATE 10-21-99

Signed by [Signature] Date DEC 2 1999
 Surveyor's Michigan License No. 23510

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
 REVISED JAN. 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1993