

SURVEY & REMONUMENTATION

APR 29 1996

REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

95 SEP -7 PM 3: 08

For corners in

LAPEER

County

Located in:
North Branch
9N 11E

Corner Code #
L-5

1. Public Land Survey	T	R	_____
	T	R	_____
	T	R	_____
	T	R	_____
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

LIBER NO. 5 PAGE NO. 271
Melissa De Vaughn
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Earl E. Gravlin July 19th 95

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

History: Burnham 1834 Post Sugar 12 N26E 25 Beech 8 S61W 13 L-5 to M-5 39.72 County Surveyor Bates 1867 Stone, Elm 3 S26.5W 41.5 Pine 34 S83.5E 18 Act 74: L4 P 372 Gravlin Fnd Mon Box S20W 34.0 Nail TP N30W 54.0 Nail 10" Elder N45E 55.15 Face Road Sign L4 P 344 Davis Fnd 1/2" Iron in Mon Box S10W 34.33 Face Utility Box N30W 53.64 Nail 10" Elder N45E 55.15 Face Road Sign S 33.00 Cap Iron 14096 Recorded Surveys L6 P742 Gravlin same as Act 74 L4 P 372, L9 P 96-97 Gravlin same as Act 74 L4 P 372, L 10 P 256 Gravlin same as Act 74 L 4 P 372, Unrecorded surveys Davis 5-20-90 90-38 Same as Act 74, L 4 P 344, Kay 78-211 10/17/78 Same as Act 74 L 4 P 372. Road Commission, N45°W 53.44' 8" Tree, N40°E 38.10' Iron, South 33.18' Iron. Drain Commission Nothing.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site Conditions: Found Boat Spike in Mon Box, Rolling Farmland, Asphalt Road East and West, Old fence row to South Gravel Road to North L-5 to M-5 2623.27 L-5 to K-5 2622.00

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 7-13-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

July 19th, 1995
FOUND BOAT SPIKE IN MON BOX, REPLACED WITH 1/2" RE-ROD AND BRASS CAP
S05°E 45.63' NAIL & TAG W SIDE 10" TWIN ELM
SOUTH 33.0' KAY ENGINEERING IRON
S50°W 47.22' NOTCH S END 24" CMP
N35°E 67.68' FACE BURIED CABLE SIGN

Signed by *Ray Davis* Date 8-17-95
Surveyor's Michigan License No. 27510