

**SURVEY & REMONUMENTATION**

OCT 29 1996

COMMISSION

REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD

96 SEP 30 PM 3:05

For corners in

LAPEER (County)	Located In:	Corner Code #
	9N 11E	M-1
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

*John DeAngelis*  
 REGISTER OF DEEDS  
 LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EARL E. GRAVLIN in a field survey on AUGUST, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

History: Corner set by Joseph Wampler, 1821. Reset or found by Parke in 1834. Witnesses Elm 16 S16°W .13 B Ash 16 N5°W .16 Set post County Surveyors Record: Book 2, page 57, no date, Stone 21-9-8, stake. Act 74 None. GLO M-1 to M-2 47.97 CH 3166.02'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site conditions: flat farmland abandoned road east & west ditch to south, fence to north. In October, 1993, Remon M-13, T10N-R11E, found 1/2" iron lying on ditchbank, apparently disturbed by recent ditch cleaning. Re-set corner on extension of North South fences in center of old East West road bed. MEASUREMENT M-1 SEC 1 T9N-R11E TO M-12 SEC 36 T10N-R11E 2632.91 AND M-1 TO M-2 3181.24.

Corner common to 3 adjoining townships.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 23510

M-1 NORTHEAST CORNER, SECTION 1, T9N-R11E  
 Found 1/2" iron with brass cap on extension of North South fences in center of old East West road bed.  
 N20°W 22.18' NAIL & TAG 6" ASH  
 S55°W 41.45' NAIL & TAG 12" ELM  
 S05°E 38.26' NAIL & TAG 20" ASH  
 N05°W 68.01' NAIL & TAG 12" ASH



APPROVED LAND CORNER  
 PA 345 OF 1990  
 LAPEER COUNTY

*Ray Davis*  
 RAY DAVIS P.S. CO. SURVEYOR  
 DATE 9-10-96

Signed by *Earle E. Gravlins* Date 9-10-96  
 Surveyor's Michigan License No. 23510