

SURVEY & REMONUMENTATION

OCT 29 1996

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 SEP 30 PM 3: 07

For corners in

<u>LAPEER</u> <small>(County)</small>	Located In:	Corner Code #
	9N 11E	M-3
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

William S. Duff
REGISTERED DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, EARL E. GRAVLIN in a field survey on AUGUST, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

History: Wampler, 1822 Set Post Cor. S. 1 & 12, Birch 18 N. 22 1/2 W. 37, Sugar 20 S. 31 1/2 W 19. County Surveyor Bates 1878 Book 2, page 57 Stone 34" long. Act 74 Liber 3, Page 524 by Gravlin. Recorded Surveys, Kay, Liber 6, Page 231-234, Found 1/2" S 22.21' Nail 10" Tree, S70°W 1.47' Nail 6" Tree, N 2.05' Nail 8" Cherry. Unrecorded Surveys, Beck-Gravlin 4-10-79, Job #187-79. GLO JOG 2.10 CH NORTH 138.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site Conditions Found 1/2" Iron. Farmland to East, Wooded to West, remains of fence going West. Fence row North and South M-2 TO M-3 2640.36, M-3 TO M-4 2630.84 AND M-3 to A-3 136.51'

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Ray Davis
RAY DAVIS H.S. CO. SURVEYOR
DATE 9-10-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 SOUTHEAST COR, SECTION 1, T9N-R11E
FOUND 1/2" IRON AT CORNER POST ON FENCE NORTH & SOUTH SET BRASS CAP
S75°W 20.04' NAIL AND TAG N/S 8" MAPLE
N15°W 18.05' NAIL AND TAG W/S 12" ASPEN
WEST 28.96' NAIL AND TAG S/S 6" ASH
N35°E 6.35' NAIL AND TAG S/S 6" ASPEN



Signed by *Earl E. Gravlin* Date 9-10-96
Surveyor's Michigan License No. 23510