

SURVEY & REMONUMENTATION

OCT 29 1996

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 SEP 30 PM 3:03

For corners in

LAPEER (County)	Located In:	Corner Code #
	9N 11E	M-4
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Michigan State Board of Land Surveyors
 REGISTER OF DEEDS
 LAPEER COUNTY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

EARL E. GRAVLIN AUGUST 96

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

History: Wampler, 1822 Set 1/2 Mile Post Beech 8 S.31W. 7 Pine 9 N.35W. 22, County Surveyor Bates 1865 Stake Sugar 22 N78E 135 Stake N87E 50. Act 74-NONE, Recorded Surveys Kay, Liber 006 Page 231-234, Found 1/2" re-rod, N10°W 4.70' Nail Triple Maple, S 1.24' Nail 8" Tree, S70°W 1.95' Nail 10" Maple, Gravlín, Liber 008, Page 832-833 Found Iron, SOUTH 1.10' 8" Ash, S60°W 1.80' 12" Oak, N10°W 4.55' Triple 12" Oak. Unrecorded Surveys, Beck-Gravlín, 4-10-79, Job # 187-79.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site Conditions: FOUND 1/2" IRON. TREE ROW NORTH AND WEST, OPEN FARM LAND.
 M-3 TO M-4 2630.84, M-4 TO M-5 2647.37 AND M-4 TO A-4 116.52

PEER GROUP
 APPROVED LAND CORNER
 PA 345 OF 1990
 LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR
 DATE 9-10-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 EAST 1/4 SECTION 12, T9N-R11E
 FOUND 1/2" IRON SET BRASS CAP
 SOUTH 1.11' NAIL AND TAG W/S 10" ASH
 N10°W 4.60' NAIL AND TAG E/S 12" TRIPLE OAK
 WEST 2.91' NAIL AND TAG N/S 5" ASH
 N45°W 0.91' NAIL AND TAG S/S 6" ASH



Signed by _____ Date 9-10-96

Surveyor's Michigan License No. 23510