

**SURVEY &
REMONUMENTATION**

APR 28 1995

REMONUMENTATION

RECEIVED FOR RECORD

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

95 SEP -7 PM 3:00

LIBER NO. 5 PAGE NO. 266
Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in

<u>LAPEER</u> (County)	Located In: North Branch 9N 11E	Corner Code # M-5
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Earl E. Gravlin July 19th 1995
I, _____, in a field survey on _____, 19____
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

History: Wampler Post 1822 Beech 8 N16W 20 Do 8 S55W 10 M5-L5 39.72 County Surveyor: Bates 1867 Stone Pine 36 N62.5W 110 Pine 30 N51W 81 M5-M4 40.08 Act 74: L004 P 371 Gravlin Fd 1/2" Iron S60E 35.04' Nail 30" Stump S25W 66.8' Nail 26" Pine S45W 45.24 Nail TP L004 P344 Davis S25W 66.77 Nail 26" Pine S45W 45.24' Nail Utility Pole S35E 44.68 24" Stump N40W 49.84 Rd Sign Post. Recorded Surveys: L009 P96-97 Gravlin Same as Act 74 L004 P371 Unrecorded Surveys: Davis 5/20/90 90-368 Same as Act 74 L004 P 344 Kay 78-211 10/17/78 Same as Act 74 L004 P 371. Road Commission, 110.2' North A-5-10-12, SW 44.6' Tele Pole, SW 66.7' Pine, SE 85.3' Maple. Nothing. Drain Commission Nothing.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site Conditions: Rolling Farmland Found 1/2" iron in Gravel Road 80.7' South of C/L Burnside Road Asphalt Road East-West Gravel Road to South M5-M6 2630.94 M5-L5 2623.27 A-5 not found.

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY
Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 7-13-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

July 19th, 1995
FOUND 1/2" RE-ROD IN PLACE, SET BRASS CAP
S25°W 67.06' NAIL & TAG E SIDE 26" PINE
S80°W 56.73' NAIL & TAG N SIDE POWER POLE
S30°E 86.51' NAIL & TAG W SIDE 24" MAPLE
S85°E 32.65' NAIL & TAG FACE BURIED CABLE SIGN

Signed by *Ray Davis* Date 8-17-95
Surveyor's Michigan License No. 23570