

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

## REMONUMENTATION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PH 1:52

LIBER NO. 05 RECORD. 112

*Melissa DeLuca*  
REGISTER OF DEEDS  
LAND RECORDS DIVISION  
MICHIGAN

For corners in	Located in:	Corner Code #
<u>Lapeer</u> <small>County</small>		
1. Public Land Survey	T <u>9N</u> R <u>11E</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Earl E. Gravlin, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Wampler 1822, P 447 Set Post, Aspin 22 S 87 W 6, Aspin 8 N 6 1/2 W 21 ACT 74 FORMS L 004, P 344 Davis N 80 W 26.24' 10" ASH, S 85 W 30.29' Post, S 55 W 43.55' POST, N 35 W 54.59' 8" ASH, L 004, P 250 GRAVLIN N 80 W 26.23' 12" ASH, S 45 W 43.51' 24" ASH, WEST 33.0' 1/2" IRON ACT 132 FORMS L 009, P 96 GRAVLIN same as 004-334, L 008, P 83 GRAVLIN same as 04-334 (M-7 - M-6 2629.58,)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C/L of Gravel Road, No occupation to West. Found 1/2" Iron M-6 to M-7 2629.69' M-6 to M-5 2630.94'

PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY

*Ray Davis*  
RAY DAVIS P.S. CO. SURVEYOR  
DATE 11-18-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

November 7, 1994  
Found 1/2" Iron, Set Brass Cap  
N 81 W 25.71' NAIL AND TAG S/S 8" ASH  
S 79.15 W 30.20' NAIL AND TAG N/S 8" WOOD POST  
S 41.16 W 43.52' NAIL AND TAG N/S 24" ASH  
N 30.24 W 54.46' NAIL AND TAG E/S 8" ASH



Signed by *Earl E. Gravlin*  
Surveyor's Michigan License No 23810

Date 11/17/94