

**SURVEY & REMONUMENTATION**

APR 28 1995

COMMISSION

**REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:54

LIBER NO. 05 PAGE NO. 114

REGISTERED PROFESSIONAL SURVEYOR  
LAWRENCE J. HARRIS

For corners in	Located In:	Corner Code #
<u>Lapeer</u> <small>(County)</small>		
1. Public Land Survey	T <u>9N</u> R <u>11E</u>	<u>M-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Earl E. Gravlin, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Wampler 1822, P 447, Set Post, Beech 11 S 85 W 6, Beech 11 N 25 W 41. ACT 74 FORMS L004, P 254 Gravlin 89 Found Iron N 45 W 45.8' 30" MAPLE, N 30 E 66.81' 36" STUMP, S 45 W 37.25' COR. POST. ACT 132 FORMS L 2, P 329 KAY same as 004-254, L 6, P 391, GRAVLIN, same as 004-254, L 8, P 83, GRAVLIN, same as 004-254. COUNTY SURVEYOR 1866, Book 2, P 53, split NE 1/4, E line 39.91 chains, NE COR Stake Pine 30", N 69 1/2 E 19.5, PINE 32", N 71 1/2 W 51, Township jog 104 links North ( 68.64'). UNRECORDED INFORMATION HBE 1993, N 45 W 47.00' NAIL 30" MAPLE, N 65 E 46.30' 4" ELM, S 45 W 54.50' POWER POLE, FOUND 1/2" IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Gravel Road West, Gravel Road North and South. Found 1/2" Iron M-7 to M-8, 2622.05' M-7 to M-6, 2629.69'

PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR  
DATE 11-18-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

November 7, 1994  
Found 1/2" Iron, Set Brass Cap  
N 45° 47' E 46.20' NAIL AND TAG N/S 6" ASPEN  
N 41° 10' W 46.88' NAIL AND TAG E/S 30" MAPLE  
S 34° 48' W 54.44' NAIL AND TAG E/S POWER POLE  
S 80° 32' E 24.86' NAIL AND TAG N/S 4" WOOD POST



Signed by

*[Signature]*

Date

11/17/94

Surveyor's Michigan License No.

23510

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 24, 1975  
REVISED JAN., 1983

LIBER 0005 PAGE 0114