

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:55

LIBER NO. 05 PAGE NO. 115
Robert D. Smith
REGISTERED PROFESSIONAL SURVEYOR
LAPORÉ & ASSOCIATES

For corners in	Located In:	Corner Code ##
<u>Lapeer</u> <small>(County)</small>		
1. Public Land Survey	T <u>9N</u> R <u>11E</u>	<u>M-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Earl E. Gravlin, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Wampler 1822, P 447, Set Post, Beech 9 S 54 1/2 W 26, Beech 7 N 24 W 2 ACT 74 FORMS L 004, P 371, 1991, Gravlin 1/2" IRON, WEST 25.10' NAIL IN COR. POST, N 89° 30' E 29.13' NAIL 30" STUMP, S 55° E NAIL TWIN MAPLE STUMP (1991) ACT 132 FORMS L 006, P 391, GRAVLIN, same as 004-371, L 005, P 195 KAY, same as 004-371, L006, P 760, GRAVLIN, same as 004-371 Kay M-8 - M-9 2632.20' COUNTY SURVEYOR 1866, Book 2, Page 53, E line 39.91 CH, Set Stake PINE 40 N 18 E 117 PINE 40 N 63 E 149.5 M-8-M-7 (2634.06') UNRECORDED INFORMATION 1966 KAY no witnesses, 1992 HBE WEST 25.25 NAIL COR POST, S 25° E 45.00' 26" BASSWOOD, S 35° W 41.00' 14" ELM, 1/2" IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Gravel Road North and South, Fence line to West. Found 1/2" Iron M-8 to M-9 2632.12' M-8 to M-7 2622.05'

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPORÉ COUNTY

Earl E. Gravlin
RAY DAVIS P.S. CO. SURVEYOR
DATE 11-18-94



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

November 7, 1994
Found 1/2" Iron, Set Brass Cap
N 42° E 39.92' NAIL AND TAG NW/SIDE 12" BASSWOOD
N 73° 27' W 24.77' NAIL AND TAG S/S 12" ELM
S 37° 46' E 44.96' NAIL AND TAG N/S 24" BASSWOOD
S 26° 38' W 40.53' NAIL AND TAG E/S 18" ELM
NORTH 89.65' 1/2" IRON, W 1/4 Cor. 19-9-12



Signed by *Earl E. Gravlin* Date 11/17/94
Surveyor's Michigan License No. 11112/94