

**SURVEY &  
REMONUMENTATION**

APR 28 1995

COMMISSION

**REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:53

LIBER NO. 05 FILE NO. 113  
*Christine DeLong*  
REGISTER OF DEEDS  
LANSING, MICHIGAN

For corners in Lapeer County Located In: Corner Code #

1. Public Land Survey	T <u>9</u> N R <u>11</u> E	M-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Earl E. Gravlin, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Wampler 1822, P 447, Set Post, Beech 9 N 25.5 W 30, Beech 5 S 82 W 21 ACT 74 FORMS L 004, P 369 Gravlin 5-20-91, Found 1/2" Iron, S 45° W 36.24' FNC POST, N 10° W 79.48' NOTCH, 18" CMP, N 55° E 38.43' NAIL FNC POST ACT 132 FORMS L 5, P 195, 3-8-79, KAY, same as L 004, P 369, L 6, P 760 GRAVLIN, same as 004-369


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Gravel Road North and South, Gravel Road West Found 1/2" IRON M-9 to M-10, 2625.76' M-9 to M-8, 2632.12'

APPROVED AND OPENED  
*[Signature]*  
DATE 11-18-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

November 7, 1994  
Found 1/2" Iron, Set Brass Cap  
N 31° 20' E 38.72' TOP 8" CMP  
N 51° W 95.67' NAIL AND TAG N/S 12" ELM  
EAST 32.54' N LEG SIGN  
N 12° 19' E 95.66' TOP 18" CMP



Signed by [Signature] Date 11/17/94  
Surveyor's Michigan License No. 23510