

SURVEY &
REMONUMENTATION

1993

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 22 PM 6:12

LIBER NO. 5 PAGE 41
LAPPEER

For corners in

LAPPEER
(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>9N</u> R <u>11E</u> | <u>M-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Earl E. Gravlin, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10. East quarter corner Section 25
History: East and South and West town lines run by Joseph Wampler, 1821. Pages 445 and 447. Subdivision of township run by Hiram Burnham, second quarter, 1834. page 455 & 456. Witnesses Cedar 18 N30°W .43 Do 26 S42.5°W .22 Set post
County Surveyors Record: Nothing in NE or SE 1/4.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site conditions: Summers Road (gravel) in cedar swamp.
Found nothing. Set iron and brass cap, by single measurement proration between M-11 and M-9
Occupation to west recent meandering stock fence 35' south, no evidence of old occupation, occupation to east 43' north.
MEASUREMENT M-10 TO M-11 2625.76, M-10 TO M-9 2625.76

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

October 24, 1993.
M-10
Found nothing. Set iron and brass cap, by single measurement proration between M-11 and M-9
N80°W 23.70' NAIL & TAG N SIDE 6" BOX ELDER
N20°W 74.18' NAIL & TAG E SIDE 10" BOX ELDER
N25°E 52.65' NAIL & TAG W SIDE 10" BOX ELDER
S15°E 55.65' NAIL & TAG W SIDE 16" CEDAR



Signed by [Signature] Date 12/01/93
Surveyor's Michigan License No. 23510