

SURVEY & REMONUMENTATION

1993

COMMISSION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD

93 DEC 22 PM 9:13

LIBER NO. 5 PAGE NO. 42
LAPPEER
MICHIGAN

For corners in

LAPPEER
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>9N</u> R <u>11E</u> | <u>M-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Earl E. Gravlin, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11. Northeast corner Section 36
History: East and South and West town lines run by Joseph Wampler, 1821. Pages 445 and 447. Subdivision of township run by Hiram Burnham, second quarter, 1834. page 455. Witnesses Cedar 8 N5°W .15, Ash 12 S58°W .28 Set Post
County Surveyors Record: Nothing in NE or SE 1/4. Recorded surveys: L002, P 201 Kay 1973

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site Conditions: Intersection Summers Road and Willis Road(both gravel) in cedar swamp(standing water)
Found 1/2" iron in place
Occupation: centerline road to west, north 26.6'(recorded .41 chains) centerline road to east.(1/2" iron)
MEASUREMENT M-11 TO M-12 2628.97', M-11 TO M-10 2625.76'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

October 24, 1993
Found 1/2" iron in place. Set brass cap
NORTH 26.60' 1/2" IRON A-11, T9N-R12E
S80°W 51.55' FACE STOP SIGN POST
N40°E 69.35' NAIL & TAG E SIDE CORNER POST
N55°E 54.30 FACE STOP SIGN POST



Signed by [Signature] Date 12/01/93

Surveyor's Michigan License No. 23510