

SURVEY &
REMONUMENTATION

1993

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 22 PM 9:15

LIBER NO. 5 FILE NO. 44
Michigan
RECORDS
LANSING

For corners in

LAPEER
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>9N</u> R <u>11E</u> | <u>M-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5	4			3		2				
3													
4	7		8	9			10		11				12
5													
6	18		17	16			15		14				13
7													
8	19		20	21			22		23				24
9													
10	30		29	28			27		26				25
11													
12	31		32	33			34		35				36
13													

I, Earl E. Gravlin, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1821 East and South and West town lines run by Joseph Wampler. Pages 445-447
1834 Subdivision of township run by Hiram Burnham, second quarter. Page 455
Witnesses: Beech 7 N69 W .45 Do 22 N71 E .17 Post Set
1974 Survey Kay Engineering, Inc., P.S. #14096; Survey Liber 2 of Surveys, Page 967 calls for "T" iron found in intersection

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site conditions: Intersection Summers Rd(gravel) and Clear Lake Road(Bit)
Found 1/2 " re-rod in monument box.
MEASUREMENT M-13 TO M-12 2628.98'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

October 26, 1993
M-13 Found 1/2 " re-rod in monument box. Set brass cap
S15°W 100.02' NAIL & TAG W SIDE 20" MAPLE
S10°E 98.85' NAIL & TAG E SIDE 18" ELM
N20°E 106.60' NAIL & TAG E SIDE GTE POLE
N20°W 126.05' NAIL & TAG E SIDE 24" MAPLE



Signed by [Signature] Date 11-24-93

Surveyor's Michigan License No. 23510