

SURVEY & REMONUMENTATION

OCT 29 1996

REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
96 SEP 30 PM 3:10

For corners in

<u>LAPEER</u> (County)	Located In:	Corner Code ##
	9N 12E	A-1
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Richard D. Smith
REGISTERED SURVEYOR
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, EARL E. GRAVLIN in a field survey on AUGUST, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

History: Corner set by Joseph Wampler, 1821. Reset or found by Parke in 1834.
Witnesses Elm 16 S16°W .13 B Ash 16 N5°W .16 Set post County Surveyors Record: Book 2, page 62, Bates 1868, no witnesses. A-1 to A-2 46.11 CH 3043.26'. Act 74 None.
GLO M-1 to M-2 T9N-R11E-47.97 CH 3166.02'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site conditions: flat farmland abandoned road east & west ditch to south, fence to north. In October, 1993, Remon M-13, T10N-R11E, found 1/2" iron lying on ditchbank, apparently disturbed by recent ditch cleaning. Re-set corner on extension of North South fences in center of old East West road bed. MEASUREMENT A-1 TO M-12 SEC 36 T10N-R11E 2632.91 AND A-1 TO M-2 T9N-R11E - 3181.24 A-1 TO A-12 T10N-R11E 3054.59
Corner common to 3 adjoining townships.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1 NORTHWEST CORNER, SECTION 6, T9N-R12E
Found 1/2" iron with brass cap on extension of North South fences in center of old East West road bed.
N20°W 22.18' NAIL & TAG 6" ASH
S55°W 41.45' NAIL & TAG 12" ELM
S05°E 38.26' NAIL & TAG 20" ASH
N05°W 68.01' NAIL & TAG 12" ASH



PEER GROUP APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY
Ray Davis
RAY DAVIS P.S. CO. SURVEYOR

Signed by *Earl E. Gravlín* Date 9-11-96
Surveyor's Michigan License No. 23510