

SECTION A
RANGE 12 EAST

MAR 29 1999

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
98 NOV 25 AM 9:27

SECTION

For corners in
LAPEER

	Located In:	Corner Code #
	BURNSIDE SOUTH	
1. Public Land Survey	T <u>9N</u> R <u>12E</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Melissa Da Vaughn
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

412

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

Earl E. Gravlin in a field survey on July 15, 19 98
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
History: 1821 West line run by Joseph Wampler. 1834 Subdivision of township by Hiram Burnham. Intersect Range Line 104 L (68.64) North Set Post Cor to 19 & 30 Pine 30 In N33E 33 Beech 8 in S7E 21. County Surveyor Record: Book 2 stake Pine 30, S77W 46, Old Pine B.L. Good, A9 to A10 39.98 (2638.68). Act 74 none. Recorded surveys, Gravlin L0011 P0637, Set Iron per G.L.O. notes, South 68.64 re-mon iron SE cor Sec 24 T9N-R11E, West 21.50 N leg of sign, N30W 70.0 SE cor tele ped. Road Commission Nothing. Gravlin A-9 to M-9 68.64, Gravlin A-9 to A-8 2653.03.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site Conditions: Rolling Farmland Found 1/2" iron Summers Road gravel North-South, Haslick Road gravel East, A-9 to A-10 2650.99, A-9 to A-8 2653.03, M-9 to A-9 North 68.64.

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

[Signature]
RAY DAVIS P.S. CO. SURVEYOR
DATE 9-17-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

NOVEMBER 9, 1998
FOUND 1/2" RE-ROD IN PLACE, SET BRASS CAP
N40°E 32.16' NOTCH 18" CMP
N46°E 55.11' NAIL & TAG NORTH SIDE 20" ELM
S29°E 40.84' NOTCH 18" CMP
S21°W 121.75' NAIL & TAG EAST SIDE POWER POLE
SOUTH 68.64' M-9



Signed by *[Signature]* Date 11-16-98
Surveyor's Michigan License No. 23510