

MAR 29 1999

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
98 NOV 25 AM 9: 28

SECTION

For corners in
LAPEER

(County)	Located In:	Corner Code #
1. Public Land Survey	Burnside South T <u>9N</u> R <u>12E</u>	<u>A-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	_____
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

4B

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Earl E. Gravlin in a field survey on July 15, 19 98
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
History: 1821 West line run by Joseph Wampler. 1834 Subdivision of township by Hiram Burnham. Corner not set. County Surveyor Record: Book 2 1867 stake Pine Stump 34, S50W 28, Pine Stump 24 N51W 60. A-10 to A-11 39.98 (2638.68), A-10 to A-9 same. Act 74 none. Unrecorded survey, Gravlin, Date 6-26-1998, Job No 980114, Set Iron, on range line at good occupation to East, S40W 46.45 nail & tag N side 6" Box Elder, N40W 35.16 nail & tag E side 10" Box Elder N60E 18.59 nail & tag W side 10" Box Elder, S10E 97.34 nail & tag W side 16" Cedar, South 43.29 to E 1/4 cor Sec 25 T9N-R11E. Road Commission Nothing. Gravlin A-10 to M-10 43.29, Gravlin A-10 to A-11 2642.46

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Site Conditions: Rolling Farmland, Set 1/2" iron on occupation to East, Summers Road gravel North-South, fence row to East, A-10 to S 1/8th line fence 1321 ±, A-10 to A-11 2642.46, A-10 to A-9 2650.99, M-10 to A-10 North 43.29.

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 9-17-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

NOVEMBER 9, 1998
FOUND 1/2" RE-ROD IN PLACE, SET BRASS CAP
S40°W 46.45' NAIL & TAG NORTH SIDE 6" BOX ELDER
N40°W 35.16' NAIL & TAG EAST SIDE 10" BOX ELDER
N60°E 18.59' NAIL & TAG WEST SIDE 10" BOX ELDER
S10°E 97.34' NAIL & TAG WEST SIDE 16" CEDAR
SOUTH 43.29' M-10



Signed by *[Signature]* Date 11-16-98

Surveyor's Michigan License No. 23510

LIBER 0006 PAGE 0088