

MAR 29 1999

REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

For corners in  
LAPEER

(County)

Located In:

Corner Code ##

Burnside South

- |                                    |   |    |   |     |      |
|------------------------------------|---|----|---|-----|------|
| 1. Public Land Survey              | T | 9N | R | 12E | A-13 |
|                                    | T |    | R |     |      |
|                                    | T |    | R |     |      |
|                                    | T |    | R |     |      |
| 2. Property Controlling in Section | S |    | T |     | R    |
|                                    | S |    | T |     | R    |
| 3. Miscellaneous Property in Sec.  | S |    | T |     | R    |
|                                    | S |    | T |     | R    |

98 NOV 25 AM 9:31

Melissa DeVaugh  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

416

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Earl E. Gravlin, in a field survey on July 15, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 History: 1821 West line run by Joseph Wampler. 1834 Subdivision of township by Hiram Burnham. Witnesses: Beech 7 N69W 45, do 22 N71E 17 Post. Act 74 Gravlin, Re-Mon L005, P044, recorded 12/22/1993. Recorded surveys, Kay Eng., L002 P967, "T" Iron, S60E 59.64 10" Ash, N65W 76.20 20" Maple, S40W 66.91 6" Cherry. Road Commission Nothing.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site Conditions: Intersection Summers Road (gravel) and Clear Lake Road (bit) Found 1/2" re-rod with cap in monument box. A-13 to A-12 2636.55 A-13 to M-12 2628.98

PEER GROUP  
 APPROVED LAND CORNER  
 PA 245 OF 1990  
 LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR  
 DATE 7-17-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

NOVEMBER 9, 1998  
 FOUND 1/2" RE-ROD WITH BRASS CAP IN MONUMENT BOX  
 S15°W 100.02' NAIL & TAG W SIDE 20" MAPLE  
 S10°E 98.85' NAIL & TAG E SIDE 18" ELM  
 N20°E 106.60' NAIL & TAG E SIDE GTE POLE  
 N20°W 126.05' NAIL & TAG E SIDE 24" MAPLE



Signed by [Signature] Date 11-16-98  
 Surveyor's Michigan License No. 23510