

SURVEY & REMONUMENTATION

OCT 29 1996

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 SEP 30 PM 3:13

For corners in

	LAPEER		Located In:		Corner Code #
	(County)		9N	12E	
1. Public Land Survey	T	R			M-1
	T	R			
	T	R			
	T	R			
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

Robert D. Wright
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EARL E. GRAVLIN, in a field survey on AUGUST, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner set by Joseph Wampler, 1821, Page 670. Witnesses Hemlock 16 S6°E .37 Do 11 N39°E .29 set post. County Surveyors Record: Nothing. Recorded surveys L004 P 175 Kay 1-9-12, Found 3/4" bar, N45°W 38.5' Nail in T.P., N45°E 34.38' Nail Wood Post, S45°E 75.47' Nail P.P., S45°W 40.39' Nail Wood Post. L004, P 178 Kay, same witnesses M-1 to M-2 2937.27. GLO M-1 to M-2 44.54 CH 2939.64'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site conditions: Good occupation, Flat farmland Intersection Stiles Road (gravel) and Cade Road (gravel) M-1 to M-12 2624.50' AND M-1 to M-2 2936.71' M-1 to L-13 2665.07' Found Iron

Corner common to 3 adjoining townships.

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Ray D. Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 9-10-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1, Northeast corner Section 1, T9N-R12E
Found 1/2 " iron in place with brass cap
N55°W 38.06' NAIL & TAG N SIDE GTE POLE
N47°E 34.98' NAIL & TAG NW FACE FENCE POST
N82°E 86.25' NAIL & TAG S SIDE 6" ELM
S45°E 75.48' NAIL & TAG SW FACE POWER POLE



Signed by *Earl E. Gravlins* Date 9-10-96
Surveyor's Michigan License No. 23510