

**SURVEY &  
REMONUMENTATION**

OCT 29 1996

COMMISSION

REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED RECORD  
95 SEP 30 PM 3:14

For corners in

LAPEER (County)	Located In:	Corner Code #
	9N 12E	M-2
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

REGISTER OF DEEDS  
LAPEER COUNTY MICHIGAN

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, EARL E. GRAVLIN AUGUST 96  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

History: Wampler, 1822 Set 1/2 Mile Post Beech 20 N.56W.32, Do. 8 S.59 1/2 W. 37, County Surveyor Bates, 1878 Stone 19.14.12 Stake. Act 74 none. Recorded Surveys, Kay, Liber 1, Page 423, Found 5/8" Hex Bar, N63°E 30.7' Spike 18" Apple, E 26.27' Spike 18" Apple, S35°E 56.58' Spike Wood Post, Kay, Liber 004, Page 178, same as Liber 1, Page 423. M-1 TO M-2 2937.27' - SANILAC COUNTY RECORDS, Huron Surveying, Inc., Liber 4, Page 68, used Hex Bar, no witness

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" HEX BAR, S45°W 2.52' FOUND 3/4" ROD, FLAT FARM LAND, GRAVEL ROAD, M-1 TO M-2 2936.71 AND M-2 TO M-3 2643.57

PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1980  
LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR  
DATE 9-10-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 EAST 1/4 CORNER, SECTION 1, T9N-R12E  
FOUND 5/8" HEX BAR, PLACED BRASS CAP ON TOP  
EAST 30.98' NAIL AND TAG S/S 18" MAPLE  
N63°E 30.98' NAIL AND TAG N/S 18" MAPLE  
S45°W 2.52' 3/4" ROD  
S85°W 29.83' NAIL AND TAG NE COR TELE PED.  
S25°E 86.80' SOUTH END C.M.P.



Signed by [Signature]  
Surveyor's Michigan License No. 23510

Date 9-10-96