

SURVEY & REMONUMENTATION

APR 29 1996

REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

95 SEP -7 PM 3:04

LIBER NO. 5 PAGE NO. 270

Melissa Daugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in

LAPEER

(County)

Located In:
Burnside South

Corner Code ##

		9N	12E						
1. Public Land Survey	T	_____	R	_____	_____	_____	_____	_____	_____
	T	_____	R	_____	_____	_____	_____	_____	_____
	T	_____	R	_____	_____	_____	_____	_____	_____
	T	_____	R	_____	_____	_____	_____	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R	_____	_____	_____	_____
	S	_____	T	_____	R	_____	_____	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____	_____	_____	_____
	S	_____	T	_____	R	_____	_____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Earl E. Gravlin July 19th 95

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

History: Parke 1834 Set Post Beech 9 S83W 16 Do 24 N41W 38 Common to A-3, County Surveyor Bates 1878 Stone 34" long No witness M-3 to M-4 40.15, Act 74 None, Recorded Surveys Kay, L1 P 423 Fnd 3/4" Re-Rod N45E 50.9 Nail 28" Maple, N80W 50.08 RR Sign, S15W 40.55 RR Sign., Unrecorded Surveys Brown 12/21/89 Job# 89-124 Fnd 3/4" bar N40E 50.80 Nail 24" Maple, S20W 40.60 RR Crossing Sign, S45E 48.6 Nail PP, Bailey Sec 7, T9N-R13E Sanilac County, 3/20/95, Job # B95-164, Fnd 5/8" Iron, N45E 51.5 PK 24" Maple, N20E 89.10 PK 30" Maple, S45E 48.58 Nail PP, N75W 50.07 SE Cor RR Sign. Road Commission, N75°W 94.10' 14" Maple, N55°E 52.33' Thornapple, S 44.05' Spike. Drain Commission Nothing.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site Conditions: Found 5/8" Rod in Gravel Intersection, Level Farmland, Gravel Road North, Gravel Road East, Asphalt Road South, Gravel Road West, M-3 to M-4 2633.33, M-3 to M-2 2643.57.

**PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY**
Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 7-13-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

July 19th, 1995
FOUND 5/8" ROD, REPLACED WITH 1/2" RE-ROD AND BRASS CAP
N20°E 89.04' NAIL & TAG W SIDE 30" MAPLE
N38°E 51.44' NAIL & TAG E SIDE 24" MAPLE
S47°E 48.43' NAIL & TAG S SIDE POWER POLE
N73°W 50.11' FACE RR CROSSING SIGN

Signed by *Earl E. Gravlin* Date 8-17-95
Surveyor's Michigan License No. 23510