

SURVEY & REMONUMENTATION

APR 29 1996

REMONUMENTATION

RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

95 SEP -7 PM 3:05

LIBER NO. 5 PAGE NO. 271

Melissa DeVaugh

REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in

LAPEER

(County)

Located In:
Burnside South

Corner Code #

9N 12E M-4

- | | | | | |
|------------------------------------|---|---|-------|-------|
| 1. Public Land Survey | T | R | _____ | |
| | T | R | _____ | |
| | T | R | _____ | |
| | T | R | _____ | |
| 2. Property Controlling in Section | S | T | R | _____ |
| | S | T | R | _____ |
| 3. Miscellaneous Property in Sec. | S | T | R | _____ |
| | S | T | R | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Earl E. Gravlin July 19th 95

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

History: Parke 1834 Set Post Maple 9 S56W 3.5 Sugar 6 N9W 25, County Surveyor Bates 1865 Stake Sugar 22 N78E 135 Stake N87E 50 M-4 to M-3 40.15, Act 74 None, Recorded Surveys None, Unrecorded Surveys Brown 12/21/89 Job # 89-124 Set Pk nail from previous surveys, East 31.4 Spike 12" Cherry, S60E 35.20 to Mon, South 11.83 W 1/4 Cor Sec 7 T9N-R13E, Brown 7/7/93 Job # 93-86 same witnesses as Job # 89-124. Road Commission, W 31.67' Wood Cor. Post, E 30.62' 12" Stump, S50°E 43.85' 14" Stump. Drain Commission Nothing.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site Conditions: Found PK Nail, Level Farmland, Asphalt Road, M-4 to M-5 2656.04, M-4 to M-3 2633.33 M-4 to A-4 South 11.83 M-4 to Empty Mon Box South 3.77.

**PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY**

Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 7-13-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

July 19th, 1995
FOUND PK NAIL, SET 1/2" IRON AND BRASS CAP IN MON BOX
S60°E 35.13' CONC. MON.
S25°E 34.33' NAIL & TAG W SIDE 12" ELM
SOUTH 11.87 1/2" RE-ROD IN MON BOX
N 25°E 73.53' NAIL & TAG W SIDE 8" ELM

Signed by *[Signature]* Date 8-17-95

Surveyor's Michigan License No. 23510

LIBER 0005 PAGE 0271