

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:57

LIBER NO. 05 PAGE NO. 117
Richard D. Bough
 REGISTER OF DEEDS
 LAFAYETTE COUNTY, MICHIGAN

For corners in	Located In:	Corner Code #
<u>Lapeer</u> <small>(County)</small>		
1. Public Land Survey	T <u>9N</u> R <u>12E</u>	<u>M-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Earl E. Gravlin, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Wampler 1822, Set Post, Lin .20, N45W 22, Birch 2.0 S56W 33

UNRECORDED INFORMATION KAY, JOB # 78-204A, 18-9-13 FND 1" AXLE SHAFT DEEP, SET 1/2" IRON, N 55°W 70.73' NAIL IN POWER POLE, N 40°W 50.37' NAIL IN COR POST, N 30°E 79.05' NAIL IN T.P., NORTH 35.90' 1/2" IRON GRAVLIN, JOB # 241-84, 18-9-13 DIVIDED ABOVE PARCEL SAME WITNESSES, SAME DISTANCE, GRAVLIN, JOB # 940489 13-9-12 SAME WITNESSES, MILLETICS JOB DATED 9-21-87 CLIENT RIC BUCKLEW, SAME WITNESSES DISTANCE M-6 TO M-7 2627.87, GRAVLIN DISTANCE M-6 to M-7, 2627.94, KAY DISTANCE M-6 TO M-7, 2627.87

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Gravel Road South, Asphalt Road North, Poor Occupation, Found 1/2" Iron M-6 to M-7 2627.84' M-6 to M-5 2627.94'

PEER GROUP
 APPROVED LAND CORNER
 PARCEL OF 1906
 LAPEER COUNTY
Ray D. Bough
 RAY DAVIS P.S. CO. SURVEYOR
 DATE 11-19-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

November 7, 1994
 Found 1/2" Iron, Set Brass Tag
 N 55°W 70.73' NAIL AND TAG S/S POWER POLE
 N 40°W 50.37' NAIL AND TAG S/S COR POST
 N 30°E 79.05' NAIL AND TAG W/S TELE POLE
 NORTH 35.40' 1/2" IRON



Signed by *Earl E. Gravlin* Date 11/19/94
 Surveyor's Michigan License No. 23510