

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

## REMONUMENTATION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:49

LIBER NO. 05 PAGE NO. 109  
*Robert D. Gray*  
REGISTERED PROFESSIONAL SURVEYOR  
LAPEER COUNTY MICHIGAN

For corners in		Located In:	Corner Code #
<u>Lapeer</u>	<u>County</u>		
1. Public Land Survey	T <u>9N</u> R <u>12E</u>		<u>M-7</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Earl E. Gravlin, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Wampler, 1822, page 631, Set Post, Ash 9 N40W 8, Birch 8 S21W 11, BURT 1834 INT, at post, Birch 10 N 42E 27, Birch 8 S 57 1/2 E 51. ACT 132 FORMS\_Kay L 3, P 347, 1975, FND 3/4" Bar EAST 30.41' NAIL IN PP, S 45° W 61.38' NAIL IN TP, S 35° E 71.16 NAIL BRACE POLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Flat farmland, gravel road, centerline road to West. Found 3/4" Bar, M-7 to M-8 2619.04' M-7 to M-6 2628.46'

PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY  
*Earl E. Gravlin*  
RAY OATES P.S. CO. SURVEYOR  
DATE 11-18-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

November 7, 1994  
Found 3/4" Bar, Replaced with 1/2" Iron with brass cap  
N 43° W 79.91' NAIL IN N/S POWER POLE,  
S 58° W 61.39' NAIL IN S/S POWER POLE,  
S 26° E 71.02' NAIL IN W/S BRACE POLE,  
EAST 30.33' NAIL IN S/S POWER POLE



Signed by *Earl E. Gravlin* Date 11-17-94

Surveyor's Michigan License No. 23510