

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:58

LIBER NO. 05 INDEX NO. 118

Richard D. Day
REGISTERED PROFESSIONAL
LAPEER COUNTY MICHIGAN

For corners in

Lapeer
County

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|-----------|---|------------|-----|
| 1. Public Land Survey | T | <u>9N</u> | R | <u>12E</u> | M-8 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Earl E. Cravlin, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Wampler, 1822, Page 631, Set Post, Ash 9 N4W 15, Maple 6 S47 1/2W 40 ACT 132 FORMS Kay, L 005, Page 199, Found 1/2" Iron, East 18.38 Notch 2' CMP, West, 22.02' Notch in 2' CMP, N 40° W 114.39' SE Cor. House

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Flat Farm Land Gravel Road, No occupation, Ditch to West. Found 1/2" Iron Rod M-8 to M-9 2619.15 M-8 to M-7 2619.04

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 11-13-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

November 7, 1994
Found 1/2" Iron Rod, Set Brass Cap
WEST 21.95' NOTCH 2' CMP
N 25° W 80.34' NAIL AND TAG E/S 8" ASH
N 57° W 114.15' FOUNDATION COR., SE COR. HOUSE
EAST 18.37' NOTCH 2' CMP



Signed by

Earl E. Cravlin

Date

11/17/94

Surveyor's Michigan License No 23510

LIBER 0005 PAGE 0118