

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:56

LIBER NO. 05 FILE NO. 116

Richard D. Davis

REGISTERED DEEDS
LAPEER COUNTY, MICHIGAN

| For corners in | Located In: | Corner Code ## |
|---------------------------------------|--------------------------|----------------|
| <u>Lapeer</u> (County) | | |
| 1. Public Land Survey | T <u>2N</u> R <u>12E</u> | <u>M-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | 17 | 18 | 19 | 20 | 21 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |

I, Earl E. Gravlin, in a field survey on September, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Wampler, 1822, P 631, Set Post, Elm 32 N35W 15, Sugar 11 S29W 37, Burt 1834, Int, W Boundry 13 links S of Post, Corrected Sugar 16 S67 1/2E 44, Ironwood 7 N22E 21, ACT 74 FORMS. ACT 132 FORMS_KAY L 005, P 199, 1979, Found 1/2" Iron, S 70°W 69.71' Nail in Power Pole, N 70°W 70.78' Nail in Power Pole, N 20°E, 53.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Flat farmland, Gravel road North-South, gravel road West, M-9 to A-9, 20.03' South Found 1/2" Iron. M-9 to M-10 2678.28' M-9 to M-8, 2519.15

PEER GROUP
APPROVED LAND CORNER
PAGE OF 100
LAPEER COUNTY
Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 11/18/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

November 7, 1994
Found 1/2" Iron, Set Brass Cap
N 65°W 70.68' NAIL AND TAG S/S POWER POLE
S 69°W 69.60' NAIL AND TAG N/S POWER POLE
S 51°W 85.08' NAIL AND TAG N/S POWER POLE
SOUTH 20.03' 1/2" IRON (A-9)
S 24°E 61.49' EAST END 18" CMP



Signed by *Earl E. Gravlin* Date 11/17/94
Surveyor's Michigan License No 23310