

SURVEY &
REMONUMENTATION

1993

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 22 PM 3:04

LIBER NO. 5
PAGE NO. 33
LAPPEER
CLERK

For corners in

LAPPEER
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>9N</u> R <u>12E</u> | <u>M-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

I, Earl E. Gravlin, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-10. East quarter corner Section 25. History: East and South town lines run by Joseph Wampler, 1821. Pages 630 and 631. Subdivision of township run by Hiram Burnham, second quarter, 1834. page 638-640. Witnesses Elm 9 N25°W 20 Sugar 14 S53°W .28 SET POST. County Surveyors Record: Nothing. Surveys(30-9-13 Kay 1/14/86 Kay 3/1/83

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site conditions: Flat farmland Cade Road(gravel) Fenceline stonerow and treeline to west. Found 1/2" iron 10.45' North(W 1/4 cor sec 30-9-13)
MEASUREMENT M-10 TO M-11 2637.59' M-10 TO M-9 2678.28' M-10 TO FENCE TO WEST 1335'NORTH

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

October 19, 1993
Found 1/2" iron 10.45' North(W 1/4 cor sec 30-9-13)
Set 1/2" iron with brass cap, on line at occupation fence to west.
N89°W 37.33' NAIL & TAG N SIDE 4" MAPLE
N38°W 45.97' NAIL & TAG N SIDE 24" HICKORY
N24°W 150.65' NAIL & TAG E SIDE POWER POLE
S21°E 73.55' NAIL & TAG W SIDE 14" ASH



Signed by [Signature] Date 12/02/93

Surveyor's Michigan License No. 23510