

**SURVEY &
REMONUMENTATION**

1993

COMMISSION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD

93 DEC 22 PM 3:06

LIBER NO. 5 FILE NO. 35
LASEP
LASEP

For corners in

LAPEER
(County)

Located In:

Corner Code ##

- | | | |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>9N</u> R <u>12E</u> | <u>M-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Earl E. Gravlin, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-12. East quarter corner Section 36. East and South town lines run by Joseph Wampler, 1821. Pages 630 and 631. Subdivision of township run by Hiram Burnham, second quarter, 1834. page 638-640. Witnesses Beech 20 North .18 Do 16 S8.5°W .19 set post. County Surveyors Record: Book 2, page 96, Southwest quarter only Recorded survey L006 P 155 Kay

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Site conditions: Flat farmland Cade Road(gravel) north south, gravel road to east.
Found 5/8" iron in place. Occupation fence to west, centerline road to east.
Appears to be common with W 1/4 corner 31-9-13.
MEASUREMENT M-12 TO M-13 2640.43 M-12 TO M-11 2640.45

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

October 19, 1993
Found 5/8" iron in place. Replaced with 1/2" iron and brass cap
S82°W 27.01 NAIL & TAG N SIDE GTE POLE
N40°W 101.51 NAIL & TAG NE SIDE POWER POLE
N41°W 296.60' SE COR METAL BLDG.
N25°W 350.09' SE COR HOUSE
N09°W 243.77' NAIL & TAG E SIDE GTE POLE



Signed by [Signature] Date 12/02/93

Surveyor's Michigan License No. 23510