

CERTIFIED
RECORDING

MAR 29 1999

1998 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in: RICH TWP.

RECEIVED FOR RECORD
98 DEC 22 PM 3:39

LAPEER Located In: Corner Code #
(County)

1. Public Land Survey T 10N R 10E B-13
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Melissa De Vaughn
REGISTER OF DEEDS
LAPEER MICHIGAN
420
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JUNE 30 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1833 GLO; PARKE, D.S.; SET 1/4 SEC. POST; BEECH 12 N53W 37 LKS, BEECH 10 N69E 29 LKS.
1989 GRAVLIN, P.S.#23510; SURVEY L.008, PG.371; SET 1/2" IRON; SOUTH 26.55' POLE, NORTH 39.37' POLE, N80°E 44.66' 8" ELM, S65°E 86.6' 6" CULVERT
1991 GRAVLIN, P.S.#23510; SURVEY L.009, PG.389-90; FND 1/2" IRON; SAME WITS AS 1989 GRAVLIN SURVEY ABOVE
1991 GRAVLIN P.S.#23510; LCRC L.004 PG.381; SAME AS 1989 GRAVLIN SURVEY ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1998 ROWE; FIELD, PS#37276; FND. 1/2" ROD W/ CAP; RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND. ROD IS IN SAME POSITION AS 1989 IRON CITED IN SECTION A ABOVE

B-13 TO A-13 1874.4' (G.L.O.) B-13 TO C-13 2640' (G.L.O.)
1887.72' (ROWE '98) 2674.30' (GRAVLIN '89, '91)
2674.24' (ROWE '98)

ACCEPTED FND. ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
B-13 SET STD. REMON CAP ON FND. 1/2" ROD
S02°E, 26.48' NAIL IN NW FACE P.POLE
N02°E, 39.35' NAIL IN E. FACE P.POLE
N13°E, 45.24' P-K NAIL W/ REMON TAG IN E. FACE 15" BEECH
S79°W, 188.84' P-K NAIL W/ REMON TAG IN NW FACE FENCE POST

PEER GROUP
APPROVED LAND CORNER
DATE 9-17-98



Signed by Jonathan M. Field Date 10-28-98
Surveyor's Michigan License No. 37276

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

a'