

MAR 29 1999

1998 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: RICH TWP.

LAPEER Located In: Corner Code #
(County)

1. Public Land Survey T 10N R 10E D-13
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

RECEIVED FOR RECORD
98 DEC 22 PM 3:41

422

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN
Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JUNE 30 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1833 GLO; PARKE, D.S.; ELM 10 INCHES IN DIAMETER COR TREE; ELM 20 N3W, ELM 10 (NO DIST'S. GIVEN)
 1906 SICKELSTEEL, C.S.; SURVEY OF SEC. 32, T10N-R10E; NOT OBJECT STATED; ELM 22 ABOUT 3 RODS NORTH OF S 1/4 32-10-10
 1990 GRAVLIN, P.S.#23510; SURVEY L.008, PG.948; REPLACED COR FROM PREVIOUS SURVEYS (1/2" IRON); N35°E 43.25' NAIL IN TELE. POLE, S50°E 52.73' R/W IRON, S60°E 56.30'E. END 12" CMP
 1993 GRAVLIN, P.S.#23510; SURVEY L.010, PG.242; FND. 1/2" IRON; SAME WITS AS 1990 SURVEY ABOVE
 1995 GRAVLIN, P.S.#23510; SURVEY L.0011, PG.0292; FND. 1/2" IRON; SAME WITS AS 1990 SURVEY ABOVE

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1998 ROWE; FIELD, PS#37276; FND. 1/2" ROD RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND. ROD IS IN SAME POSITION AS 1989 IRON CITED IN SECTION A ABOVE

- D-13 TO C-13 2640' (G.L.O.) D-13 TO E-13 2640' (G.L.O.)
 2649.04' (GRAVLIN '93) 2649.08' (GRAVLIN '90, '95)
 2649.11' (ROWE '98) 2648.87' (ROWE '98)
- D-13 TO D-1 184.80' (AVG. G.L.O.)
 172.96' (ROWE '98)

PEET GROUP
APPROVED FOR CORNER
DATE 9-17-98

ACCEPTED FND. ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 D-13 SET STD. REMON CAP ON FND 1/2" ROD
 EAST, 172.96' FND. 1/2" ROD
 N31°E, 43.24' NAIL IN E. FACE P.POLE
 S52°E, 52.57' S. FACE FENCE POST
 S35°E, 75.60' P-K NAIL W/ REMON TAG IN NE FACE FENCE POST
 S56°W, 97.60' P-K NAIL W/ REMON TAG IN NW FACE FENCE POST



Signed by Jonathan M. Field Date 10-28-98
Surveyor's Michigan License No. 37276