

MAR 29 1999

1998 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: RICH TWP.

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>10E</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD  
98 DEC 22 PM 3:42

423

Melissa DeVaugh  
REGISTER OF DEEDS  
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, JONATHAN M. FIELD, in a field survey on JUNE 30 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
1833 GLO; PARKE, D.S.; SET POST; SUGAR 14 N67E 21 LKS, BEECH 20 N73 1/2W 44 LKS.  
1906 SICKLESTEEL, C.S.; SURVEY SEC. 32, T10N-R10E; PG. 106-107; STAKE; BALM OF GILLEAD 4 N59W 120 LKS.  
1906 SICKLESTEEL, C.S.; SURVEY SEC. 33, T10N-R10E; PG. 108-109; NO OBJECT STATED, NO WITS GIVEN  
1976 BECK, P.S.#21559; SURVEY L.003, PG.782-3; NO OBJECT STATED; S45°W 64.1' P-K NAIL IN TEL POLE, N60°W 38.1' BOLT IN S. FACE GUARD POST  
1980 BECK, P.S.#21559; SURVEY L.005, PG.775; MONUMENT BOX; SAME WITS AS 1976 SURVEY ABOVE  
1980 BECK, P.S.#21559; SURVEY L.006, PG.10; MONUMENT BOX; SAME WITS AS 1976 SURVEY ABOVE  
1985 GRAVLIN, P.S.#23510; SURVEY L.007, PG.156-7; MON BOX; SAME WITS AS 1976 SURVEY ABOVE  
1989 GRAVLIN, P.S.#23510; LCRC L.004, PG.260; FND. MON BOX; SAME WITS AS 1976 SURVEY ABOVE  
1990 GRAVLIN, P.S.#23510; SURVEY L.008, PG.948; MON BOX; SAME WITS AS 1976 SURVEY ABOVE  
1993 GRAVLIN, P.S.#23510; SURVEY L.010, PG.148-9; FND. MON BOX; SAME WITS AS 1976 SURVEY ABOVE  
1995 GRAVLIN, P.S.#23510; SURVEY L.0011, PG.0292; FND. MON BOX; SAME WITS AS 1976 SURVEY ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1998 ROWE; FIELD, PS#37276; FND. 1/2" ROD RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND. ROD IS IN SAME POSITION AS 1976 IRON CITED IN SECTION A ABOVE

E-13 TO D-13	2640' (G.L.O.) 2649.08' (GRAVLIN '90, '95) 2648.87' (ROWE '98)	E-13 TO F-13	2640' (G.L.O.) 2653.51' (GRAVLIN '85) 2653.66' (ROWE '98)
E-13 TO E-1	192.72' (G.L.O.) 190.90' (ROWE '98)		

DEED GROUP  
PROPERTY CORNER  
EVIDENCE

*[Signature]*

REGISTERED PROFESSIONAL SURVEYOR  
DATE: 9-17-98

ACCEPTED FND. ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
E-13 SET STD. REMON CAP ON FND. 1/2" ROD  
EAST, 190.90' FND. 1/2" ROD  
S48°W, 63.76' P-K NAIL IN NE FACE P.POLE  
S72°E, 190.77' P-K NAIL IN W. FACE P.POLE  
N54°W, 37.29' BOLT IN S. FACE GUARD POST  
N59°E, 198.81' SW CORNER OF BRICK HOUSE

Signed by *Jonathan M. Field* Date 10-28-98  
Surveyor's Michigan License No. 37276



α