

MAR 29 1999

SECTION

1998 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: RICH TWP.

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>10E</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD

98 DEC 22 PM 3:43

Melissa DeVaugh  
REGISTER OF DEEDS  
LAPPEER COUNTY, MICHIGAN

424

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, JONATHAN M. FIELD, in a field survey on JUNE 30 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1833 GLO; PARKE, D.S.; SET 1/4 SEC. POST; ELM 20 N36 1/2W 44 LKS, ELM 24 N71 1/2E 73 LKS.  
1906 SICKLESTEEL, C.S.; SURVEY SEC. 33, T10N-R10E; PG. 108-109; NO OBJECT STATED, NO WITS GIVEN  
1985 GRAVLIN, P.S.#23510; SURVEY L.007, PG.156-7; 1/2" IRON; S45°E 24.0' W/E HDWL., N20°E 20.10' 6" MAPLE, N60°E 35.75' 6" ELM  
1991 GRAVLIN, P.S.#23510; LCRC L.004, PG.375; FND. 1/2" IRON; SAME WITS AS 1985 SURVEY ABOVE

REGISTER GROUP  
APPROVED LAND CORNER  
BY \_\_\_\_\_  
DATE \_\_\_\_\_

JONATHAN M. FIELD  
PROFESSIONAL SURVEYOR  
DATE 9-17-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 ROWE; FIELD, PS#37276; FND. 1/2" ROD RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND. ROD IS IN SAME POSITION AS 1985 IRON CITED IN SECTION A ABOVE

F-13 TO E-13	2640' (G.L.O.)	F-13 TO G-13	2640' (G.L.O.)
	2653.51' (GRAVLIN '85)		2653.51' (ROWE '98)
	2653.66' (ROWE '98)		
F-13 TO F-1	173.91' (AVG. G.L.O.)		
	173.49' (ROWE '98)		

ACCEPTED FND. ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 SET STD. REMON CAP ON FND. 1/2" ROD  
EAST, 173.53' FND. 1" PIPE  
S45°E, 24.85' W. EDGE OF HEADWALL  
N56°E, 59.45' NAIL W/ FLAG. IN SW FACE FENCE POST  
N25°E, 19.89' P-K NAIL IN W. FACE 18" MAPLE  
N46°W, 34.71' NAIL IN SW FACE 20" ELM

Signed by Jonathan M. Field Date 10-28-98  
Surveyor's Michigan License No. 37276

