

**SURVEY &
REMONUMENTATION**

MAY 28 1997

COMMISSION

**1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 DEC 27 PM 1:14

Melvin DeVaugh
REGISTER OF DEEDS
LAPPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

For corners in RICH TWP.

<u>LAPPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>T9N</u> R <u>R10E</u>	<u>H-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on AUGUST 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
 1833 GLO; PARKE, D.S.; SET 1/4 POST; BEECH 24 N73 1/2E 70LKS., SUGAR 8 N46W 5LKS.
 1906 SICKLESTEEL, C.S.; SURVEY OF NW 1/4 SEC.34; STAKE; PINE 48 S64W 106LKS., SUGAR 20 S11E 9LKS.
 1974 KAY ENG.; KAY, P.S.#14096; SURVEY L.003, PG.149; FND IRON ROD 1.0' DEEP; S70W 56.99' NAIL 8" OAK; NORTH 32.04' NAIL IN FENCE POST; N75E 94.05' NAIL 4" ELM
 1975 KAY ENG.; KAY, P.S.#14096; SURVEY L.003, PG.204; FND IRON ROD 1.0' DEEP; SAME WITS AS 1974 SURVEY ABOVE
 1977 BECK-GRAVLIN; GRAVLIN, P.S.#23510; SURVEY L.004, PG.161; FND 1/2" ROD; SAME WITS AS 1974 SURVEY ABOVE

GLO NOTES OF T9N-R10E IMPLY THAT THIS CORNER IS NOT COMMON WITH H-1 T9N-R10E

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1996 ROWE ENG.; FIELD, P.S.#37276; FND 1/2" ROD AT C/L CASTLE RD. E-W & ON FENCE LINE & TREE ROW TO N. RECOVERED 2 PREVIOUS WITNESSES INDICATING THAT FND ROD IS IN THE SAME POSITION AS 1974 ROD CITED ABOVE

H-13 TO G-13 2647.90'
H-13 TO I-13 2652.76'

ACCEPTED FND 1/2" ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPPEER COUNTY,
Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 8-27-96

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 H-13 SET STANDARD REMON CAP ON FND 1/2" ROD
 N05°W, 27.42' P-K NAIL IN W. FACE 6" ELM
 S65°E, 52.60' P-K NAIL IN SW FACE TRI 8" ELM
 S05°W, 19.72' SET NAIL W/REMON TAG IN E. FACE 12" ELM
 S60°W, 57.03' P-K NAIL IN NW FACE TRI 8" OAKS
 EAST, 106.06' FND. 1/2" ROD



Signed by *Jonathan M. Field* Date 12-2-96
Surveyor's Michigan License No. 37276