

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

**1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 DEC 27 PM 1:25

For corners in RICH TWP.

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>10E</u>	<u>I-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on AUGUST 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

- A. Description of original monument and accessories and/or subsequent restoration:
1833 GLO; PARKE, D.S.; SET POST; BEECH 9 N35W 8LKS., BEECH 11 N19E ?LKS.
1906? SICKLESTEEL, C.S.; SURVEY IN SEC.35; STAKE; W. OAK 36 N64 1/2W 148LKS., PINE 40 S41W 164LKS.
1974 KAY ENG.; KAY, P.S.#14096; SURVEY L.003, PG.149; NOT FND.
1975 KAY ENG.; KAY, P.S.#14096; SURVEY L.003, PG.204; NOT FND.
1977 BECK-GRAVLIN; GRAVLIN, P.S.#23510; SURVEY L.004, PG.161; NOT FND.

GLO NOTES OF T9N-R10E INDICATE THAT THIS CORNER IS NOT COMMON WITH I-1 T9N-R10E

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996 ROWE ENG.; FIELD, P.S.#37276; FND NO EVIDENCE OF CORNER MONUMENTATION; SET 1/2" ROD AT INTERSECTION OF EXISTING FENCELINE RUNNING N. AND LINE FROM J-13 THROUGH I-1 OF T9N-R10E

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

I-13 TO H-13 2652.76'
I-13 TO J-13 2657.96'

Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 12-27-96

ACCEPTED POSITION THUS ESTABLISHED AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-13 SET 1/2" ROD W/ STANDARD REMON CAP

N10°E, 23.46' SET NAIL W/REMON TAG IN E. FACE 38" MAPLE
S05°E, 26.76' SET NAIL W/REMON TAG IN E. FACE 26" MAPLE
S50°W, 37.22' SET NAIL W/REMON TAG IN NW FACE 20" MAPLE
N60°W, 50.46' SET NAIL W/REMON TAG IN SW FACE 6" ELM
EAST, 63.70' FND. 1/2" ROD IN MON. BOX



Signed by *Jonathan M. Field*
Surveyor's Michigan License No. 37276

Date 12-2-96