

**SURVEY &
REMONUMENTATION**

MAY 28 1997

COMMISSION

**1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 DEC 27 PH 1:24

Melissa De Vaughn
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

For corners in <u>RICH TWP.</u>	Located In:	Corner Code #
<u>LAPEER</u>		
(County)		
1. Public Land Survey	T <u>10N</u> R <u>10E</u>	<u>J-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on AUGUST 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1833 GLO; PARKE, D.S.; SET 1/4 POST; B. ASH 20 N86W 3LKS.; B. ASH 20 N60 1/2E 22LKS.

GLO NOTES OF T9N-R10E IMPLY THAT THIS CORNER IS NOT COMMON WITH J-1 T9N-R10E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996 ROWE ENG.; FIELD, P.S.#37276; FND NO EVIDENCE OF CORNER MONUMENTATION; SET 1/2" ROD AT INTERSECTION OF EXISTING FENCE LINE TO N. AND LINE FROM K-13 THROUGH J-1 OF T9N-R10E

J-13 TO I-13 2657.96'
J-13 TO K-13 2670.68'

ACCEPTED POSITION THUS ESTABLISHED AS BEST EVIDENCE OF ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 SET 1/2" ROD W/ STANDARD REMON CAP IN MON. BOX
EAST, 37.12' FND. 3/4" PIPE IN MON. BOX
S30°E, 32.16' TOP CENTER OF CONC. PILLAR
N65°E, 39.48' W. EDGE OF W. SIGN POST LEG
N55°W, 22.01' SET 1/2" ROD W/CAP #37276
S50°W, 22.33' SET 1/2" ROD W/CAP #37276
S65°E, 104.61' SET P-K NAIL W/REMON TAG IN SW FACE P.POLE



Signed by Jonathan M. Field Date 12-2-96
Surveyor's Michigan License No. 37276 PEER GROUP

APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

LIBER 0005 PAGE 0385

RAY DAVIS P.S. CO. SURVEYOR
DATE 12-27-96