

**SURVEY &  
REMONUMENTATION**

APR 28 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC 22 PM 2: 07

LIBER NO. 05 PAGE NO. 183  
*Nelma De Kough*  
REGISTER OF DEEDS  
LANSING, MICHIGAN

For corners in RICH TWP.  
LAPEER Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey	T 10N R 10E	K-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on SEPTEMBER 23 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1834 GLO; BURNHAM, D.S.; SET POST; BEECH 12 S33W 29LKS., BEECH 10 N11E 11LKS.  
1906 SICKLESTEEL, C.S.; STAKE; PINE 56 N80E 305LKS., PINE 48 S55E 215LKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1994 ROWE ENG.; FIELD, P.S.#37276; FND NO EVIDENCE OF MONUMENT AT CORNER; FND NO EVIDENCE OF GLO OR SICKLESTEEL WITNESSES; FND REMNANTS OF N-S FENCE S. OF C/L DODDS RD.  
SET 1/2"X 18" ROD AT INTERSECTION OF N-S FENCE LINE EXTENDED AND C/L OF DODDS ROAD  
ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
K-11 SET 1/2"X 18" ROD W/ STANDARD BRASS CAP  
S40°W, 31.76' SET NAIL W/REMON TAG IN SE FACE 8" CHERRY  
S15°W, 26.87' SET NAIL W/REMON TAG IN E. FACE 10" MAPLE  
N50°W, 35.30' SET NAIL W/REMON TAG IN SW FACE 8" MAPLE  
N50°E, 40.07' SET NAIL W/REMON TAG IN W. FACE 4" APPLE IN CLUMP  
S60°E, 23.39' SET 1/2" ROD W/CAP #37276



PEEP GROUP  
APPROVED FOR CORNER  
*J. Field*  
Surveyor's Michigan License No. 37276  
LAPEER COUNTY

Date 12-8-94

RAY C. S. S. CO. SURVEYOR  
DATE 12-22-94

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 22, 1971  
REVISED MAY 14, 1975  
REVISED JAN. 1982  
ADAPTED FOR WORD PROCESSING MARCH, 1993