

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

**1994 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC 22 PM 2:09

LISER NO. 05 PAGE NO. 185
Melissa DeLoach
REGISTER OF DEEDS
LANSING, MICHIGAN

| | | |
|---|-------------|---------------|
| For corners in RICH TWP. LAPPEER (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T 10N R 10E | L-11 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, JONATHAN M. FIELD, in a field survey on SEPTEMBER 23 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; BURNHAM, D.S.; SET 1/4 POST; BEECH 10 N15W 16LKS., BEECH 6 S30E 28LKS.

NO FURTHER RECORD FOUND

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994 ROWE ENG.; FIELD, P.S.#37276; FND 1/2" ROD OVER BENT 1/2" PIPE AT C/L ASPHALT ROAD N-S &
ON C/L GRAVEL ROAD E-W

2639'+/- L-11 TO APPARENT L-10 (FENCE TO W. AT 1315'+/- N.)
2618'+/- L-11 TO M-11

ACCEPTED 1/2" ROD AND PIPE AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER
POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-11 REMOVED 1/2" ROD & PIPE, SET 1/2" X 18" ROD W/ STANDARD BRASS CAP IN MON. BOX
N45°E, 44.55' SET NAIL W/REMON TAG IN SE FACE 12" COR POST (LEANS NNE'LY)
S45°E, 35.44' SET 1/2" ROD W/CAP #37276
S50°W, 37.40' SET 1/2" ROD W/CAP #37276
N50°W, 34.90' SET 1/2" ROD W/CAP #37276



Signed by PEER GROUP *M.F.O.* Date 12-8-94
APPROVED LAND CORNER
Surveyor's Michigan License No. 37276
LAPPEER COUNTY

RAY DAY S.P.S. CO. SURVEYOR
DATE 12-22-94

LIBER 0005 PAGE 0185